


SCHEDULE OF QUANTITY

Estimated Cost	99000.00
Earnest Money	2000.00
Time :-	Fifteen days

NAME OF WORK :- Maintenance of Pinjore Baddi Nalagarh Swarght road NH- 21A (New NH -105) Km 35/0 to 66/275 (SH:- Hiring of Hydraulic excavator for breaking of big boulders from km 52/0 to 66/275)

Sr.No.	Description of items	Quantity	Rate in Figures	Rate in Words	Unit	Amount	Overall percntage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount
1	Hiring of L & T komatsu PC 210 crawler mounted Hydraulic excavator with breader for cuttig works tec, Including carrige of material with all lead and lift and as per direction of Ebngineer in Charge.	22.00 hr.	4500.00	Rupees Four Thousand Five Hundred Only	Per Hour	99000.00	
	Total :-					99000.00	



 Executive Engineer,
 NH Division, HPPWD., Solan

SCHEDULE OF QUANTITY

Estimated Cost	77103
Earnest Money Rs.	1600
Time :-	One Month

NAME OF WORK :-Maintenance of road NH-05 on Kalka Shimla Wangtoo road Km 131/0 to 145/100 (SH:- Providing and laying Theroplastic paint at Tutikandi junction)

Sr.No.	Description of items	Quantity	Rate in Figures	Rate in Words	Unit	Amount	Overall percntage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount
1	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC : 35.The finished surface to be level, uniform and free streaks and holes.	98.85 m2	780.00	Rupees Seven hundred eighty only	Per sqm	77103.00	
					G.Total	77103.00	



 Executive Engineer, NH
 Division, HPPWD Solan

SCHEDULE OF QUANTITY

Estimated Cost	98631
Earnest Money Rs.	2000
Time :-	One Month

NAME OF WORK :--Maintenance of road NH-05 on Kalka Shimla Wangtoo road Km 0/00 to 13/00 (SH:- Providing and laying Theroplastic paint at Km 7/000 to 13/000)

Sr.No.	Description of items	Quantity	Rate in Figures	Rate in Words	Unit	Amount	Overall percntage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount
1	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC : 35.The finished surface to be level, uniform and free streaks and holes.	126.45 m2	780.00	Rupees Seven hundred eighty only	Per sqm	98631.00	
					G.Total	98631.00	


Executive Engineer, NH
Division, HPPWD Solan

SCHEDULE OF QUANTITY

Estimated Cost	99294
Earnest Money Rs.	2000
Time :-	One Month

NAME OF WORK :--Maintenance of road NH-05 on Kalka Shimla Wangtoo road Km 0/00 to 13/00 (SH:- Providing and laying Theroplastic paint at Km 2/500 to 6/500)		Earnest Money Rs.	2000
		Time :-	One Month
Sr.No.	Description of items		

Sr.No.	Description of items	Quantity	Rate in Figures	Rate in Words	Unit	Amount	Overall percentage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount
1	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC : 35.The finished surface to be level, uniform and free streaks and holes.	127.30 m2	780.00	Rupees Seven hundred eighty only	Per sqm	99294.00	
					G.Total	99294.00	


Executive Engineer, NH
Division, HPPWD Solan

SCHEDULE OF QUANTITY

Estimated Cost	98436
Earnest Money Rs.	2000
Time :-	One Month

NAME OF WORK :--Maintenance of road NH-05 on Kalka Shimla Wangtoo road Km 131/00 to 145/100 (SH:- Providing and laying Theroplastic paint at Shoghi Barrier)

Sr.No.	Description of items	Quantity	Rate in Figures	Rate in Words	Unit	Amount	Overall percntage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount
1	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC : 35.The finished surface to be level, uniform and free streaks and holes.	126.20 m2	780.00	Rupees Seven hundred eighty only	Per sqm	98436.00	
					G.Total	98436.00	


Executive Engineer, NH
Division, HPPWD Solan

SCHEDULE OF QUANTITY

							Estimated Cost	95641.00
							Earnest Money	2000.00
							Time :-	One Month
NAME OF WORK :- Maintenance of Pinjore Baddi Nalagarh Swarght road NH- 21A (New NH -105) Km 35/0 to 66/275 (SH:- Providing and fixing Steel railing on Chikni-IV Bridge at km 37/722)								
Sr.No.	Description of items	Quantity	Rate in Figures	Rate in Words	Unit	Amount	Overall percntage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount	
1	Hiring of L & T komatsu PC 210 crawler mounted Hydraulic excavator with breader for cutting works etc., as per CPWD specification/SOR 2020 including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	285.00 kg	108.00	Rupees One Hundred & Eight Only	Per Kilogramme	30780.00		
2	Providing and fixing 40 mm dia MS Pipe in railing (three rows of MS pipe as per CPWD specification/SOR 2020 including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	150.00 m	420.00	Rupees Four Hundred & Twenty Only	Per Running meter	63000.00		
3	Finishing with Epoxy paint (two or more coats) On Steel work at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. Complete including all lead lift and carriage of material by all mode of transportation as per satisfaction and direction of the Engineer-In-Charge.	16.92 m ²	110.00	Rupees One Hundred & Ten Only	Per Square meter	1861.00		
Total:-						95641.00		


 Executive Engineer,
 NH Division, HPPWD., Solan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed percentage basis tenders are hereby invited by Executive Engineer, NH Division, HP.PWD. Solan on behalf of Governor of Himachal Pradesh for the following works from the approved registered Contractors of appropriate class (D) enlisted with Himachal Pradesh Public Works Department, whose registration stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:-

	Tender Schedule	Date	Time
1.	The last date for receipt of application for tender Form.	28-11-2025	1:00 PM
2.	The last date for issue of tender Form	28-11-2025	4:00 PM
3.	The last date for receipt of tender.	29-11-2025	10:30 AM
4.	The date of opening of tender.	29-11-2025	11:00 AM

The tender forms can be obtained against payment of Rs.350/- (Non refundable) and contractor will be required to produce documents of registration in appropriate class, list of completed works and GST registration certificate. The tenders shall be opened in presence of contractor or their authorized representative.

The earnest money in shape of National Saving Certificate/Time deposit account of nationalized saving or Saving Bank account in any of the post offices and F.D.R. of Nationalized Bank duly pledged in favour of the Executive Engineer, NH Division, HP.PWD, Solan must accompany with the tender offer. The exemption from depositing the earnest money with each tender earlier granted has been withdrawn under Govt. Notification No. PWE (B&R)(B)14(18) / 98-11 dated 4.11.2003 and accordingly the tender received without Earnest Money shall be rejected without assigning any reasons thereto and shall not be entertained.

The tenders will be issued only to them who qualify the criteria after the scrutiny of application Form. The tenders not accompanying the Earnest money shall be rejected at the time of opening. The contractor shall also indicate the detail of Earnest money in the tender document. The request on prescribed application should accompany the registration of appropriate class, GST registration No. work done certificate. The tenders shall be opened on schedule date and time in presence of contractor or in the presence of the authorized representative.

The validity of tenders has been given in the tender document. If any contractor/firm withdraw the offer within validity period then their earnest money shall be forfeited and shall finally be at the disposal of State Govt. The contractors are advised to write the percentage both in figures and in words, failing which the tender shall be rejected.

Conditional and incomplete tenders shall out rightly be rejected.

Application for obtaining the tender form must accompany the latest renewal of enlistment and proof of GST No/NOC from Excise and Taxation Department regarding Tax clearance. The offer shall be kept open for 15 days.

If due to any unforeseen reasons the office of the Executive Engineer, NH Division, HP.PWD, Solan remain closed on the notified date of sale and receipt of tender, the tender will be sold and received/opened on next working day at same specified time.

The Executive Engineer reserves the right to accept or reject the tender without assigning any reason.

Description of Jobs:-

Sr. No.	Name of work	Estimated Cost (in Rs)	Earnest Money	Time
1	Maintenance of Pinjore Baddi Nalagarh Swarghat road NH 21-A (New NH-105) km 35/0 to 66/275 (SH:-Hiring of Hydraulic	Rs.99,000/-	Rs. 2000/-	Fifteen Days

	excavator for breaking of binf boulders from km 52/275)			
2	Maintenance of road of NH 05 Kalka Shimla Wangtoo road km 131/00 to km 145/100 (SH:-Providing and laying thermoplastic paint at Tutu Kandi junction)	Rs.77,103/-	Rs. 1,600/-	One month
3	Maintenance of road of NH 05 Kalka Shimla Wangtoo road km 0/00 to 13/00 (SH:-Providing and laying thermoplastic paint at 7/000 to 13/00)	Rs.98,631/-	Rs. 2000/-	One month
4	Maintenance of road of NH 05 Kalka Shimla Wangtoo road km 0/0 to 13/00 (SH:-Providing and laying thermoplastic paint at km 2/500 to 6/500)	Rs.99,294/-	Rs.2000/-	One month
5	Maintenance of road of NH 05 Kalka Shimla Wangtoo road km 131/00 to 145/100 (SH:-Providing and laying thermoplastic paint at Shoghi Barrier)	Rs.98,436/-	Rs.2000	One month
6	Maintenance of Pinjore Baddi Nalagarh Swarghat road NH 21-A (New NH-105) km 35/0 to 66/275 (SH:-Providing and fixing steel railing on Chikni-IV Bridge at km 37/722)	Rs.95,641/-	Rs.2000/-	One month
7				

Term and Conditions:-

The contractor will have to produce following documents and attach attested copies of the same at the time of submitting application for issue of tender Form.

- Enlistment/renewal in appropriate class in HP.PWD.
- PAN Card issued by the Income Tax Department.
- Proof of valid GST Registration.
- Statement showing the ongoing works in HP.PWD.
- E.P.F registration.

Certified that the above work is of emergent nature in exigency of Public Interest.

Executive Engineer,
Solan NH Division,
HP.PWD., Solan

Dated:-

No. NHD/CB/TA/NIT/2025-26- 3987-4025

Copy forwarded to the following for information and necessary action:-

- The Chief Engineer, NH, HP.PWD, Shimla.
- The Superintending Engineer, NH Circle, HPPWD Shimla
- All the Assistant Engineers under this Division.
- The Executive Engineer, IT Cell in the o/o Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.
- Various registered contractors working under this Division
- Notice Board.

Executive Engineer,
Solan NH Division,
HP.PWD., Solan.