

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NO. PWP/CB/Tender Notice/2025-26- 7691-92
To

Through e-mail
eeict-pwd-shi@hp.gov.in
Dated:- 21-11-2025

The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.
eeict-pwd-shi@hp.gov.in

Subject :- Regarding publication of Tender Notice on departmental website to be opened on 27.11.2025.

Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature due to rainy season and in the public interest.

Enclosures:- Notice Inviting tender and schedule of quantity. (30 Nos.)



Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.

Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Scaled Percentage rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 27.11.2025 up to 02.30 PM and shall be opened on 27.11.2025 the same day at 3.00 P.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 1.00 PM on 27.11.2025 for which the applications should reach in this office up to 04.00 PM on 26.11.2025. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1	Repair & Restoration of rain damages on Girinagar to Jatton road Km. 0/0 to 25/0. (SH:- Construction of Retaining wall in cement concrete at RD. 2/645 to 2/665) Under PDNA-2023	Rs. 4,38,409/-	Rs. 9000/-	Two Months.	350/-	C & D
2	Repair & Restoration of rain damages on Jamta Rajban road Km. 23/0 to 43/0. (SH:- Construction of Retaining wall in cement concrete at RD.24/950 to 24/966) Under PDNA-2023.	Rs. 4,34,896/-	Rs. 9000/-	Two Months.	350/-	C & D
3	Repair & Restoration of rain damages on Badrinagar Jamniwala Parduni road Km. 15/100 to 19/760. (SH:- Construction of Retaining wall in cement concrete from RD. 18/388 to 18/400 & Bed concrete under slab culvert at RD. 18/396) Under PDNA-2023.	Rs. 4,79,077/-	Rs. 10000/-	Three Months.	350/-	C & D
4	Repair & Restoration of rain damages on Badrinagar Jamniwala Parduni road Km. 15/100 to 19/760. (SH:- Repair of RCC Slab Culvert abutment, Bed concrete, Railing at RD.18/750)	Rs. 4,88,152/-	Rs. 10000/-	Three Months.	350/-	C & D

	Under PDNA-2023.					
5	Repair & Restoration of rain damages on link road to village Lohgarh km. Km. 0/0 to 5/150. (SH:- Construction of Edge wall in cement concrete at RD. 0/790 to 0/820, Retaining wall in wire crate at RD.0/915 to 0/925) & U-shape drain at RD. 0/790 to 0/820) Under PDNA-2023.	Rs. 4,58,718/-	Rs. 9500/-	Three Months.	350/-	C & D
6	Repair & Restoration of rain damages on Mehat Gawana Khali Achhon Naddi road Km. 0/0 to 12/0. (SH:-. Construction of Breast wall wall in cement concrete at RD.4/560 to 4/590) Under PDNA-2023.	Rs. 4,34,525/-	Rs. 9000/-	Two Months.	350/-	C & D
7	Repair & Restoration of rain damages on Mehat Gawana Khali Achhon Naddi road Km. 0/0 to 12/0. (SH:-. Construction of Breast wall in cement concrete at RD.1/300 to 1/332) Under PDNA-2023.	Rs. 4,64,840/-	Rs. 10,000/-	Two Months.	350/-	C & D
8	Repair & Restoration of rain damages on Kolar Bilaspur road Km. 0/0 to 12/0. (SH:-. Construction of Retaining wall in wire crate at RD. 10/630 to 10/667) Under PDNA-2023.	Rs. 3,07,866/-	Rs. 6500/-	Two Months.	350/-	C & D
9	Repair & Restoration of rain damages on Kolar Bilaspur road Km. 0/0 to 12/0. (SH:-. Construction of Retaining wall in wire crate at RD.2/650 to 2/670) Under PDNA-2023.	Rs. 3,63,080/-	Rs. 7500/-	Three Months.	350/-	C & D
10	Repair & Restoration of rain damages on Kolar Bilaspur road Km. 0/0 to 12/0. (SH:-. Repair of Pot holes by providing WMM and 20 mm thick premix carpet km. 0/0 to 5/0) Under PDNA-2023.	Rs. 4,99,848/-	Rs. 10000/-	Three Months.	350/-	C & D
11	Repair & Restoration of rain damages on Kolar Bilaspur road Km. 0/0 to 12/0. (SH:-. Repair of Pot holes by providing WMM and 20 mm thick premix carpet km. 6/0 to 11/0) Under PDNA-2023.	Rs. 4,72,103/-	Rs. 9500/-	Three Months.	350/-	C & D

12	Repair & Restoration of rain damages on Badrinagar Jamniwala Parduni road Km. 16/0 to 19/760 & various road of Majra Section. (SH:- Repair to Pot holes by 20 mm thick premix carpet in km. 16/0 to 19/0 & various road of Majra Section). Under MMSRRY.	Rs. 4,76,179/-	Rs. 10000/-	Four Months.	350/-	C & D
13	Link road from NH-07 via Bhaderkali Mandir to Forest check post Kolar Bilaspur road km.0/00 to 2/400. (SH:- Preparation of Technical sanction estimate, working estimate and DNIT)	Rs. 38,400/-	Rs. 800/-	One Month.	350/-	C & D
14	Repair & Restoration of rain damages link road Jamniwala to Khara road km. 0/0 to 6/800. (SH:- Providing and laying interlocking tile in km. 5/300 to 5/391). Under PDNA 2023.	Rs. 4,86,184/-	Rs. 10000/-	Two Months.	350/-	C & D
15	Restoration of rain damages to Paonta Puruwala Singhpura Bhagani Gojjar Dakpathar road km. 0/0 to 26/500.(SH:- Providing and laying 80 mm thick interlocking paver blocks in km. 14/012 to 14/050 and 14/062 to 14/087).Under PDNA 2023.	Rs. 4,99,436/-	Rs. 10000/-	Two Months.	350/-	C & D
16	Restoration of rain damages to Paonta Puruwala Singhpura Bhagani Gojjar Dakpathar road km. 0/0 to 26/500.(SH:- Providing and laying 80mm thick interlocking paver blocks in km. 14/087 to 14/100 and 14/112 to 14/162).Under PDNA 2023.	Rs. 4,97,464/-	Rs. 10000/-	Two Months.	350/-	C & D
17	Restoration of Rain Damages to Paonta Puruwala Singhpura Bhagani Gojjar Dak Pathar Road (MDR-94) km. 0/0 to 26/500 (SH:- Extension of existing 2.00 meter Span RCC Slab Culvert at Km. 1/350 along with Wing Wall) Under PDNA 2023.	Rs. 1,99,531/-	Rs. 4000/-	Two Months.	350/-	C & D
18	Repair & Restoration of rain damages to link road from Bainkuan to Kishanpura road km. 0/0 to 1/440. (SH- Construction of Retaining wall in cement concrete at RD 0/210 to 0/227) Under PDNA-2023	Rs. 4,99,548/-	Rs. 10000/-	Two Months.	350/-	C & D

19	Repair & Restoration of rain damages to link road from Bainkuan to Kishanpura road km. 0/0 to 1/440. (SH- Construction of Retaining wall in cement concrete at RD 0/170 to 0/187) Under PDNA-2023	Rs. 4,99,915/-	Rs. 10000/-	Two Months.	350/-	C & D
20	Repair & Restoration of rain damages to link road from Majra Bridge to Bias Mandir road km. 0/0 to 2/340. (SH- construction of Retaining wall in cement concrete at RD 1/773 to 1/790) Under PDNA-2023	Rs. 4,99,915/-	Rs. 10000/-	Two Months.	350/-	C & D
21	Repair & Restoration of rain damages to Paonta Puruwala Singhpura Bhagani Gojjar Dak Pathar Road (MDR-94) km. 0/0 to 26/500 (SH:- Providing and laying 80mm thick interlocking paver blocks in km. 221/595 to 21/660) Under PDNA 2023.	Rs. 4,97,735/-	Rs. 10000/-	One Month.	350/-	C & D
22	Repair & Restoration of rain damages to Paonta Puruwala Singhpura Bhagani Gojjar Dak Pathar Road (MDR-94) km. 0/0 to 26/500 (SH:- Providing and laying 80mm thick interlocking paver blocks in km. 16/840 to 16/905) Under PDNA 2023.	Rs. 4,98,857/-	Rs. 10000/-	One Month.	350/-	C & D
23	Restoration of rain damage to Paonta to Rampurghat road km. 0/0 to 5/0. (SH- Providing and laying 80 mm thick interlocking paver blocks in km 2/550 to 2/550 to 2/565 & 2/885 to 2/898) Under PDNA 2023.	Rs. 499872/-/-	Rs. 10000/-	Two Months.	350/-	C & D
24	Repair & Restoration of rain damages to link road Jamniwala to Khara road km. 0/0 to 6/800 (SH- Providing and laying interlocking tile in km 5/392 to 5/496) Under PDNA 2023.	Rs. 4,97,909/-	Rs. 10000/-	Two Months.	350/-	C & D
25	Repair & Restoration of rain damages on Jamnighat Jheelbankabara to Dhounwala road km. 0/0 to 5/020 (SH- Construction of Retaining wall in wire crate from RD 4/050 to 4/068.50)	Rs. 4,80,389/-	Rs. 10000/-	Two Months.	350/-	C & D

26	Repair & Restoration of rain damages to Kolar Bilaspur road km. 0/0 to 12/00 (SH- Providing and laying 80mm thick interlocking paver blocks in km. 0/300 to 0/400) Under PDNA 2023.	Rs. 4,99,384/-	Rs. 10000/-	Two Months.	350/-	C & D
27	Repair & Restoration of rain damages to Kolar Bilaspur road km. 0/0 to 12/00 (SH- Providing and laying 80mm thick interlocking paver blocks in km. 5/080 to 5/170) Under PDNA 2023.	Rs. 4,99,117/-	Rs. 10000/-	Two Months.	350/-	C & D
28	Repair & Restoration of rain damages to Paonta Puruwala Singhpora Bhagani Gojjar Dak Pathar Road (MDR-94) km. 0/0 to 26/500 (SH:- Providing and laying 80mm thick interlocking paver blocks in km. 21/735 to 21/790) Under PDNA 2023.	Rs. 4,23,304/-	Rs. 10000/-	Two Months.	350/-	C & D
29	Repair & Restoration of rain damages to Paonta Puruwala Singhpora Bhagani Gojjar Dak Pathar Road (MDR-94) km. 0/0 to 26/500 (SH:- Providing and laying 80mm thick interlocking paver blocks in km. 14/165 to 14/220) Under PDNA 2023.	Rs. 4,22,655/-	Rs. 9500/-	Two Months.	350/-	C & D
30	Repair & Restoration of rain damages to Jagatpur Parduni road km. 0/0 to 5/00 (SH-Providing and laying 80 mm thick interlocking paver blocks in km. 0/775 to 0/885) Under PDNA 2023.	Rs. 4,97,340/-	Rs. 10000/-	Two Months.	350/-	C & D

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature due to Rainy Season and in public interest.

Conditions:-

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number, Permanent Account Number and EPF Number.
3. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
4. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.

5. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
6. The contractor / Firms are requested to insert the percentage rate in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
7. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills along with proof of ownership of JCB/Affidavit from owner of JCB and Tractor with Trolley on hire basis.
8. GST Clearance Certificate from GST Department and up to date filling return as per instruction issued by the GST Department.
9. The contractor should apply for two works only at a time for tenders

Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.

Dated:- 21-11-2025

No.PWP/CB-Tender Notice/2025-26- 7693-7742

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
10. Notice Board.

Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib

Job-1.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on Gili Nagar to Jalton road Km 0/0 to 25/0 (SI):- Construction of Retaining wall in cement concrete at RD 2/645 to 2/665) Under PDNA-2023

Estimated cost:-438409/-only
Estimated Money:-30000/-only
Time:-Two Months

Sl No	Sub heads and items of work.	Qty	Unit	Figures	Rate in Words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	51.20	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	9728
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering : All work up to plinth level 1:4:10 (1 Cement : 4 coarse sand : 10 graded stone aggregate 40 mm nominal size) including cartage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	03.40	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	413264
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with stop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including cartage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	16.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	5872
4	Providing and Laying filter media with granular crushed aggregate as per specification to thickness of not less than 600mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment wing wall, return wall to the full height compacted to firm condition complete as per drawing and technical specification, including all eads lifts and cartage of materials, as per the direction of Engineer-in-charge.	8.30	Per cubic metre	1150.00	Rupees One thousand one hundred fifty and paise nil only	9545
Total						438409

DNT No./26 for the Year 2025-26, Checked & approved for Rs 438409/-Only

Executive Engineer
Peonia(B&R)Division
UP.PWD, Prayagraj

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on Jamta Rajban road Km 23/0 to 43/0 (SH:- Construction of Retaining wall in cement concrete at RD 24/950 to 24/966) Under PDNA-2023

Estimated cost:-434896/-only

Estimated Money:-9000/-only

Time:-Two Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	54.72	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	10397
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	83.20	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	412273
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	3670
	Providing and Laying filter media with granular crushed aggregate as per specification to thickness of not less than 600mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment wing wall ,return wall to the full height compacted to firm condition complete as per drawing and technical specification. including all eads lifts and carriage of materials, as per the direction of Engineer-In charge.	7.44	Per cubic metre	1150.00	Rupees One thousand one hundred fifty and paise nil only	8556
Total						434896

DNIT No. 149 for the Year 2025-26, Checked & approved for Rs 434896/-Only

Draft Schedule of Quantity

Estimated cost:-479077/-only
Estimated Money:-10000/-only
Time:-Three Months

Name of Work:- Repair & Restoration of rain damages on Badrinagar Jammiwala Parduni Road Km 15/100 to 19/760. (SH:-
Construction of Retaining wall in cement concrete from RD 18/388 to 18/400 & Bed concrete under slab culvert at RD
18/396) Under PDNA-2023.

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	33.12	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	6293
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	70.20	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	347855
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge..	19.91	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	117585
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	20.00	Per Nos	367.20	Rupees Three hundred sixty seven and paise twenty only	7344
Total						479077

DNIT No. 135 for the Year 2025-26, Checked &
approved for Rs 479077/-Only

Associate Engineer
Paonta(B&R)Div/414
4P PWD PaontaS.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on Badrinagar Jamniwala Parduni Road Km 15/100 to 19/760. (SH:-
 Repair of RCC Slab Culvert abutment, bed concrete, railing at RD 18/750) Under PDNA-2023.

Estimated cost:-488152/-only

Estimated Money:-10000/-only

Time:- Three Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	26.62	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	5058
2	Providing and laying Cement Concrete 1:1.5:3 (One cement :One and half sand : Three aggregate) for plain /rain forced cement concrete in super structure M-25 grade as per grade & technical specification clause 802,803,1202 & 1204. including centering & shuttering, including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	20.92	Per Cubic metre	7850.00	Rupees Seven thousand eight hundred fifty and paise nil only	164222
3	Supplying, fitting & placing HYSD bar reinforcement in Super structure complete as per drawing & technical Specifications clause 1002, 1010 & 1202 including cost of binding wire including carriage of materials within all leads, lifts & other incidental charges & as per direction of Engineer-in-Charge.	2076.00	Per Kilogram	98.00	Rupees Ninety eight and paise nil only	203448
4	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	30.25	Per Cubic metre	3125.10	Rupees Three thousand One hundred twenty five and paise ten only	94534

Job No 4

P-1

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on Badrinagar Jarniwaia Parduni Road Km 15/100 to 19/760. (SH:-
Repair of RCC Slab Culvert abutment, bed concrete, railing at RD 18/750) Under PDNA-2023.

Estimated cost:-488152/-only
Estimated Money:-10000/-only
Time:-Three Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	26.62	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	5058
2	Providing and laying Cement Concrete 1:1.5:3 (One cement :One and half sand : Three aggregate) for plain /rain forced cement concrete in super structure M-25 grade as per grade & technical specification clause 802,803,1202 & 1204, including centering & shuttering, including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	20.92	Per Cubic metre	7850.00	Rupees Seven thousand eight hundred fifty and paise nil only	164222
3	Supplying, fitting & placing HYSD bar reinforcement in Super structure complete as per drawing & technical Specifications clause 1002, 1010 & 1202 including cost of binding wire including carriage of materials within all leads, lifts & other incidental charges & as per direction of Engineer-in-Charge.	2076.00	Per Kilogram	98.00	Rupees Ninety eight and paise nil only	203448
4	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	30.25	Per Cubic metre	3125.10	Rupees Three thousand One hundred twenty five and paise ten only	94534

5	Steel work welded in gratings including cutting, hosting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. the rate including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government. including hauling of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	204.80	Per Kilogramme	102.00	Rupees One hundred two and paise nil only	20890
Total						488152

DNIT No 129 for the Year 2025-26, Checked &
approved for Rs 488152-Only


Executive Engineer,
B&R Division,
HP, PWD, Poonja Sahib.

5	Steel work welded in gratings including cutting, hosting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. the rate including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government. including hauling of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	204.80	Per Kilogramme	102.00	Rupees One hundred two and paise nil only	20890
				Total		488152

DNIT No 129 for the Year 2025-26, Checked &
approved for Rs 488152/-Only


Executive Engineer,
B&R Division,
HP, PWD, Patna Sahib.

5	Steel work welded in gratings including cutting, hosting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. the rate including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government. including hauling of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	204.80	Per Kilogramme	102.00	Rupees One hundred two and paise nil only	20890
Total						488152

DNIT No 129 for the Year 2025-26, Checked &
approved for Rs 488152/-Only


Executive Engineer,
B&R Division,
HP, PWD, Patna Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on link road to Village Lohgarh Km 0/0 to 5/150 (SH:- Construction of Edge wall in cement concrete at RD 0/790 to 0/820, Retaining wall in wire crate at RD 0/915 to 0/925) & U-Shape drain at RD 0/790 to 0/820) Under PDNA-2023

Estimated cost:-458718/-only
Estimated Money:-9500/-only
Time:-Three Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	33.60	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	6384
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five killogramme) each complete including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	56.88	Per Cubic metre	3125.10	Rupees Three thousand One hundred twenty five and paise ten only	177756
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth leve l :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	50.73	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	251377
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth leve l :3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	3.60	Per cubic metre	5424.85	Rupees Five thousand four hundred twenty four and paise eighty five only	19529

...ing weapholes in brick masonry / stone masonry /plain reinforced concrete
...outment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with
of the structures with stop of 1(V):20(H) towards drawing face complete as per drawing and
technical specification clauses 614, 709, 1204.3.7 including cartage of materials with in
all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-
charge.

10.00	Per Nos	367.20	Rupees Three hundred sixty seven and paise twenty only	3672
Total				458718

DNIT No/28 for the Year 2025-26, Checked &
approved for Rs 458718/-Only

Executive Engineer,
B&R Division,
HP.PWD, Pagnia Sahib.

Job No-6

Draft Schedule of Quantity

Estimated cost:-434525/-only
Estimated Money:-9000/-only
Time:-Two Months

Name of Work:-Repair & Restoration of rain damages on Mehat Gawana Khali Achhon Nadi road Km 0/0 to 12/0 (Sh:-
Construction of Breast wall in cement concrete at RD 4/560 to 4/590)Under PDNA-2023

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	49.80	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	9462
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	84.30	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	417723
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	20.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	7340
Total						434525

DNT No. 143 for the Year 2025-26, Checked &
approved for Rs 434525/-Only

Executive Engineer,
Raonia(B&R) Division,
RD PWT, Raonia Sar,

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on Mehat Gawana Khail Achhon Nadi road Km 0/0 to 12/0 (SH:- Construction of Breast wall in cement concrete at RD 1/300 to 1/332) Under PDNA-2023

Estimated cost:- 464840/-only
Estimated Money:- 10000/-only
Time:- Two Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	53.12	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	10093
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	89.92	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	445572
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	25.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	9175
Total						464840

DNIT No/ 33 for the Year 2025-26, Checked & approved for Rs 464840/-Only

Executive Engineer,
Paonta (B&F) Division,
JP PWT, Paonta Sahib

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on Kolar Bilaspur road Km 0/0 to 12/0 (SH:- Construction of Retaining wall in wire crate at RD 10/630 to 10/667) Under PDNA-2023

Estimated cost:-307866/-only
Estimated Money:-6500/-only
Time:-Two Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	30.00	Per cubic metre	190.00	Rupees One hundred ninty and paise nil only	5700
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads,lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	96.69	Per Cubic metre	3125.10	Rupees Three thousand One hundred twenty five and paise ten only	302166
Total						307866

DNIT No. 125 for the Year 2025-26, Checked & approved for Rs 307866/-Only

Executive Engineer,
B&R Division,
HP.PWD, Raonta Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on Kolar Bilaspur road Km 0/0 to 12/0 (SH:- Construction of Retaining wall in wire crate at RD 2/650 to 2/670) Under PDNA-2023

Estimated cost:-363080/-only
Estimated Money:-7500/-only
Time:-Three Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	40.00	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	7600
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads,lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	113.75	Per Cubic metre	3125.10	Rupees Three thousand One hundred twenty five and paise ten only	355480
Total						363080

DNT No. 14/ for the Year 2025-26, Checked & approved for Rs 363080/-Only

Executive Engineer,
B&R Division,
HP.PWD, Paonta Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on Kolar Bilaspur road Km 0/0 to 12/0 (SH:- Repair of Pot holes by providing WMM and 20mm thick premix carpet Km 0/0 to 5/0) Under PDNA-2023.

Estimated cost:-499848/-only
Estimated Money:-10000/-only
Time:-Three Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53mm to 0.075mm)to wet mix macadam specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub-base/base course on well prepared surface and compacting with vibratory roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406., as directed by Engineer-in-charge.	58.13	Per cubic metre	2394.00	Rs Two Thousand three hundred ninety four and paise nil only	139163
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm thick pre-mix carpet and seal coat type B specification clause 1904.2 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	1007.50	Per square metre	358.00	Rupees Three hundred fifty eight paise nil only	360685
Total						499848

DNT No/34 for the Year 2025-26, Checked & approved for Rs 499848/-Only


Executive Engineer,
B&R Division,
HP.PWD, Papnla Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages on Kolar Blisspur road Km 0/0 to 12/0 (SH:- Repair of Pot holes by providing WMM and 20mm thick premix carpet Km 6/0 to 11/0) Under PDNA-2023.		Estimated cost:-472103/-only
		Estimated Money:-9500/-only
		Time:-Three Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53mm to 0.075mm)to wet mix macadam specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub-base/base course on well prepared surface and compacting with vibratory roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406., as directed by Engineer-in-charge.	58.13	Per cubic metre	2394.00	Rs Two Thousand three hundred ninety four and paise nil only	139163
2	Repair to pot holes and removal of loose material, trimming of sides ,cleaning of surface by providing tack coat, 20mm thick pre-mix carpet and seal coat type B specification clause 1904.2 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	930.00	Per square metre	358.00	Rupees Three hundred fifty eight paise nil only	332940
Total						472103

DNIT No/37 for the Year 2025-26, Checked & approved for Rs 472103/-Only

Executive Engineer,
B&R Division,
HP.PWD, Ronta Sahib.

Page 12

Draft Schedule of Quantity

Name of Work:-Repair of Badripur Jamniwala Parduni road Km 16/0 to 19/760 & Various road of Majra Section, (SH:- Repair to pot holes by 20mm thick premix carpet in Km 16/0 to 19/0 & various road of Majra Section). under MMSRRY.

Estimated cost:-476179/-only

Estimated Money:-10000/-only

Time:-Four Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 (eighty to hundred) KN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, 63 to 40mm size watering and compacting to the required density grading 3(Three) as per Technical Specification Clause 405 by manual means, WBM Grading-II, including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	11.02	Per cubic metre	2374.40	Rupees Two thousand three hundred seventy four and paise forty only	26164
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm thick pre-mix carpet and seal coat type B specification clause 1904.2 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	1321.63	Per square metre	340.50	Rupees Three hundred forty and paise fifty only	450015
Total						476179

DNIT No. 38 for the Year 2025-26, Checked & approved for Rs 476179/-Only

Executive Engineer,
B&R Division,
HP.PWD, Rohta Sahib.

Draft Schedule of Quantity

Name of Work:-Link road from NH 07 via Bhaderkaili mandir to forest check post Kolar Bilaspur Road km 0/000 to 2/400. (SH:-
Preparation of Technical sanction estimate, Working estimate and DNIT)

Estimated cost:-38400/-only
Estimated Money:-800/-only
Time:-One Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Preparation of Technical sanction. The Work will be carried in accordance with latest design specification, latest market rate and to satisfaction of Engineer-in-charge. Printing two set complete in all respect and submitting the same to division office and there after approval from competent authority	2.400	Per Kilometer	7000	Rupees Eight thousand and paise nil only	16800
2	Preparation of Working Estimate. The Work will be carried in accordance with latest design specification, latest market rate and to satisfaction of Engineer-in-charge. Printing two set complete in all respect and submitting the same to division office and there after approval from competent authority	2.400	Per Kilometer	5000	Rupees Six Thousand and paise nil only	12000
3	Preparation of DNIT. The Work will be carried in accordance with latest market rate and to satisfaction of Engineer-in-charge. Printing two set complete in all respect and submitting the same to division office and there after approval from competent authority	2.400	Per Kilometer	4000	Rupees Five thousand and paise nil only	9600
Total						38400

DNIT Noted for the Year 2025-26, Checked & approved for Rs 38400/-Only

Executive Engineer,
B&R Division,
HP.PWD, Poonja Sahib.

1. The first part of the report is a summary of the work done during the year. It is a brief statement of the main results of the work, and is intended to give a general impression of the progress made.

2. The second part of the report is a detailed account of the work done during the year.

The first part of the report is a summary of the work done during the year. It is a brief statement of the main results of the work, and is intended to give a general impression of the progress made. The second part of the report is a detailed account of the work done during the year. It is a more complete statement of the work, and is intended to give a more detailed impression of the progress made. The third part of the report is a summary of the work done during the year. It is a brief statement of the main results of the work, and is intended to give a general impression of the progress made. The fourth part of the report is a detailed account of the work done during the year. It is a more complete statement of the work, and is intended to give a more detailed impression of the progress made.

The first part of the report is a summary of the work done during the year. It is a brief statement of the main results of the work, and is intended to give a general impression of the progress made.

The second part of the report is a detailed account of the work done during the year. It is a more complete statement of the work, and is intended to give a more detailed impression of the progress made.

The third part of the report is a summary of the work done during the year. It is a brief statement of the main results of the work, and is intended to give a general impression of the progress made.


The fourth part of the report is a detailed account of the work done during the year. It is a more complete statement of the work, and is intended to give a more detailed impression of the progress made.

The fifth part of the report is a summary of the work done during the year. It is a brief statement of the main results of the work, and is intended to give a general impression of the progress made.

Approved by
s per

4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge..	2.83	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	16714
Total						486184

DNIT No. 163 for the Year 2025-26, Checked & approved for Rs 486184/-Only


Executive Engineer,

B&R Division,

HP.PWD Raonta Sahib.

~~HP.PWD, Raonta Sahib.~~

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Paonta Puruwalla Singhpura Bhagani Gojjar Dak Pathpathar road km 0/0 to 26/500 (SH:- Providing and laying 80 mm thick interlocking paver blocks in km 14/012 to 14/050 and 14/062 to 14/087) under PDNA 2023

Estimated cost :- Rs :- 4,99,436/-
Earnist Money:- Rs:- ~~2,000/-~~ 1,500/-
Time:- Two Months.

Sr. No.	Description of items	Quantity	unit	Rate		Amount
				Figure	Words	
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	28.35	Per cubic metre	5023.80	Rs. Five thousand twenty three & paise eighty only	142425.00
2	Providing and laying of 80 mm thick ISI mark interlocking concrete block pavements complete as per drawing and Technical Specification close 1504 including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	346.50	Per Square metre	959.20	Rs. Nine hundred fifty nine & paise twenty only	332363.00
3	Plain/reinforced cement concrete in open foundations complete as per drawings and technical specification Clauses 802, 803, 1202 & 1203 (RCC grade M 20 Nominal mix (1:2:4) (one cement: two sand: four graded crushed alone aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	3.75	Per Cubic metre	6,572.70	Rs. Six thousand five hundred seventy two & paise seventy only	24648.00
Total:						499436.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.
- 2). Signature of the contractor with full address:-

Executive Engineer,
Paonta (B&R) Division
HP PWD
Paonta Sahib

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Paonta Puruwalla Singhpura Bhagani Gojjar Dak Pathpathar road km 0/0 to 26/500 (SH:- Providing and laying 80 mm thick interlocking paver blocks in km 14/087 to 14/100 and 14/112 to 14/162) under PDNA 2023

Estimated cost :- Rs :- 4,97,464/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No.	Description of items	Quantity	unit	Rate		Amount
				Figure	Words	
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	28.35	Per cubic metre	5023.80	Rs. Five thousand twenty three & paise eighty only	142425.00
2	Providing and laying of 80 mm thick ISI mark interlocking concrete block pavements complete as per drawing and Technical Specification close 1504 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	346.50	Per Square metre	959.20	Rs. Nine hundred fifty nine & paise twenty only	332363.00
3	Plain/reinforced cement concrete in open foundations complete as per drawings and technical specification Clauses 802, 803, 1202 & 1203 (RCC grade M 20 Nominal mix (1:2:4) (one cement: two sand: four graded crushed alone aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	3.45	Per Cubic metre	6,572.70	Rs. Six thousand five hundred seventy two & paise seventy only	22676.00
Total:						497464.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.
- 2). Signature of the contractor with full address:-

Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages to Paonta Puruwalla Singhpura Bhagani Gofjar Dak Pathpathar road (MDR-94) km 0/0 to 26/500
(SH:- extension of existing 2.00 meter Span RCC slab culvert at km 1/350 along with wing wall) under PDNA 2023

Estimated cost :- Rs :- 1,99,531/-
Earnist Money:- Rs:- 4,000/- Time:-
Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earth work in excavation for structure as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	5.25	Per cubic metre	203.00	Rs. Two hundred three & paise Nil only	1066.00
2	Providing and laying concrete 1:3:6 (1 cement: 3 sand: 6graded stone aggregate of 20mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	9.66	Per cubic metre	5750.00	Rs. Five thousand Seven hundred fifty & paise Nil only	55545.00
3	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 . P.C.C. grade M 20 Nominal mix (1:2:4) (one cement: two sand: four graded crushed alone aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	13.84	Per Cubic metre	6,572.00	Rs. Six thousand five hundred seventy two & paise Nil only	90956.00
4	Providing and laying Plain/reinforced cement concrete in sub structure complete as per drawing and technical specification clauses 802,804,805,806,807,1202 and 1204 R.C.C. grade M-25) 1:1.5:3 including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1.22	Per Cubic metre	7580.00	Rs. Seven thousand five hundred eighty & paise Nil only	9248.00
5	Supplying, fittings and placing HYSD bar reinforcement in super structure complete as per clause 1002,1010 & 1202 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	0.411	Per tonne	103000.00	Rs. One lac three thousand & paise Nil only	42333.00
6	Providing and laying Filter media with granular stone aggregate as per specification to a thickness not less than 600(six hundred millimetre) mm with smaller size toward the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing walls, return walls to the full height compacted to firm condition complete as per drawing and technical specification clause 1204.38, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	0.68	Per Cubic metre	563.90	Rs. Five hundred sixty three & paise ninety only	383.00
Total :-						199531.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

- Condition :-
- 1). The Rates should be quoted for all heights including all leads and lifts.
 - 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.
- Signature of the contractor with full address:-

Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damage to link road from Bainkuan to Kishanpura road km 0/0 to 1/440. (SH:- Construction of Retaining wall in cement concrete at RD 0/210 to 0/227) Under PDNA-2023

Estimated cost:- 499548/-only
Estimated Money:- 10000/-only
Time:- Two Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	58.14	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	11047
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand : 6 leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	86.02	Per cubic metre	5424.85	Rupees Five thousand four hundred twenty four and paise eighty five only	466646
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	28.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	10276
4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	38.34	Per cubic metre	302.00	Rupees Three hundred two and paise nil only	11579
		Total				499548

DNIT No. 161 for the Year 2025-26, Checked & approved for Rs 499548/-Only

Executive Engineer,
B&R Division,
HP.PWD, Raonta Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damage to link road from Bainkuan to Kishanpura road km 0/0 to 1/440. (SH:- Construction of Retaining wall in cement concrete at RD 0/170 to 0/187) Under PDNA-2023

Estimated cost:-499915/-only
Estimated Money:-10000/-only
Time:-Two Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	58.14	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	11047
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	86.02	Per cubic metre	5424.85	Rupees Five thousand four hundred twenty four and paise eighty five only	466646
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	29.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	10643
4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	38.34	Per cubic metre	302.00	Rupees Three hundred two and paise nil only	11579
Total						499915

DNIT No. 15 for the Year 2025-26, Checked & approved for Rs 499915/-Only

Executive Engineer,
B&R Division,
HP.PWD, Raonta Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damage to link road from Majra Bridge to Bias mandir road km 0/0 to 2/340.
(SI:- Construction of Retaining wall in cement concrete at RD 1/1773 to 1/1790) Under PDNA-2023

Estimated cost:-499915/-only
Estimated Money:-10000/-only
Time:-Two Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	58.14	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	11047
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	86.02	Per cubic metre	5424.85	Rupees Five thousand four hundred twenty four and paise eighty five only	466646
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	29.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	10643
4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	38.34	Per cubic metre	302.00	Rupees Three hundred two and paise nil only	11579
Total						499915

DNIT No. 166 for the Year 2025-26, Checked & approved for Rs 499915/-Only

Executive Engineer,
B&R Division,
HP.PWD, Raonla Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages to Paonta Puruwalla Singhpura Bhagani Gojjar Dakpather road km 0/0 to 26/500. (SH:- Providing and laying 80mm thick interlocking paver blocks in km 21/595 to 21/660) Under PDNA-2023

Estimated cost:-497735/-only
Estimated Money:-10000/-only
Time:-One Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	29.25	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	144940
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	357.50	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	339625
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge..	2.23	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	13170
Total						497735

DNT No. 117 for the Year 2025-26, Checked & approved for Rs 497735/-Only

Executive Engineer,
B&R Division,
HP.PWD, Paonta Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages to Paonta Puruwalla Singhpura Bhagani Gojjar Dakpather road km 0/0 to 26/500. (SH:- Providing and laying 80mm thick interlocking paver blocks in km 16/840 to 16/905) Under PDNA-2023

Estimated cost:-498857/-only
Estimated Money:-10000/-only
Time:-One Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1 :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	29.25	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	144940
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	357.50	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	339625
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge..	2.42	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	14292
Total						498857

DNIT No. 168 for the Year 2025-26, Checked & approved for Rs 498857/-Only

Executive Engineer,
B&R Division,
HP.PWD, Paonta Sahib.

Draft Schedule of Quantity

Name of Work:-Restoration of rain damage to Paonta to Rampurghat road Km 0/0 to 5/0.(SH:- Providing and laying 80mm thick interlocking paver blocks in km 2/550 to 2/565 & 2/885 to 2/898) Under SDRF/NDRF.

Estimated cost:-499872/-only
Estimated Money:-10000/-only
Time:-Two Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	5.85	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	1112
2	Construction of granular sub-base course with local material by mix in place method construction of granular sub base by providing local material spreading in uniform layer with motor grader on prepared surface mixing by in place method with rotavator at once and compacting with smooth to achieve the desired density, complete as per Technical Specification Clause 401.4 as per technical specification clause 408 using gravel mix soil. including haulage of materials with in all leads, lifts and carriage of materials and as per the direction of the Engineer-in Charge.	29.40	Per cubic metre	1931.25	Rupees One thousand nine hundred thirty one and paise twenty five only	56779
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	32.72	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	162134

	and laying factory made chartered edge Cement Concrete paver blocks in drain, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	278.35	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	264433
5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in- charge. .	2.61	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	15414
				Total		499872

DNIT No/19 for the Year 2025-26, Checked &
approved for Rs 499872/-Only

Executive Engineer,
B&R Division,
HP.PWD, Paonta Sahib.

Draft Schedule of Quantity

Name of Work:- Repair and Restoration rain damage to link road Jamnivala to Khara road km 0/0 to 6/800 (SH:- Providing and laying interlocking tile in Km 5/392 to 5/496) Under PDNA 2023.

Estimated cost:-497909/-only

Estimated Money:-10000/-only

Time:-Two Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	25.48	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	126258
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	353.60	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	335920
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	6.05	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	35730
Total						497909

DNIT No. 154 for the Year 2025-26, Checked &

approved for Rs 497909/-Only

Executive Engineer,

B&R Division,

HP.PWD Raonta Sahib.

Draft Schedule of Quantity


Name of Work:-Repair & Restoration of rain damages on Jamnighat Jheelbankabara to Dhounwala road Km 0/0 to 5/020 (SH:-
Construction of Retaining wall in wire crate from RD 4/050 to 4/068.50)Under PDNA-2023

Estimated cost:-480389/-only
Estimated Money:-10000/-only
Time:-Two Months

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	37.00	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	7030
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads,lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	151.47	Per Cubic metre	3125.10	Rupees Three thousand One hundred twenty five and paise ten only	473359
Total						480389

DNT No/57 for the Year 2025-26, Checked &
approved for Rs 480389/-Only

Executive Engineer,
B&R Division,
HP.PWD Raonta Sahib.



Draft Schedule of Quantity


Name of Work:-Repair & Restoration of rain damages on Jamnighat Jheelbankabara to Dhounwala road Km 0/0 to 5/020 (SH:- Construction of Retaining wall in wire crate from RD 4/050 to 4/068.50)Under PDNA-2023						Estimated cost:-480389/-only
						Estimated Money:-10000/-only
						Time:-Two Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	37.00	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	7030
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg/ Twenty five kilogramme) each complete including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	151.47	Per Cubic metre	3125.10	Rupees Three thousand One hundred twenty five and paise ten only	473359
Total						480389

DNIT No. 57 for the Year 2025-26, Checked &
approved for Rs 480389/-Only


Executive Engineer,

B&R Division,

HP.PWD, Paonta Sahib.



Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages to Kolar Bilaspur road km 0/0 to 12/00. (SH:- Providing and laying 80mm thick interlocking paver blocks in km 0/300 to 0/400) Under PDNA-2023

Estimated cost:-499384/-only
Estimated Money:-10000/-only
Time:-Two Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	19.78	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	98014
2	Providing and laying factory made charnfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	384.20	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	364990
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	6.16	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	36380
Total						499384

DNIT No. 16/ for the Year 2025-26, Checked & approved for Rs 499384/-Only

Executive Engineer,
B&R Division,
HP.PWD, Bonta Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages to Kolar Biliapur road km 0/0 to 12/00. (SH:- Providing and laying 80mm thick interlocking paver blocks in km 5/080 to 5/170) Under PDNA-2023

Estimated cost:-499117/-only
Estimated Money:-10000/-only
Time:-Two Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	20.25	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	100343
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	387.00	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	367650
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	5.27	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	31124
Total						499117

DNIT No/58 for the Year 2025-26, Checked & approved for Rs 499117/-Only

Executive Engineer,
B&R Division,
HP.PWD Raonla Sahib.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages to Paonta Puruwalla Singhpura Bhagani Golljar Dakpather road km 0/0 to 26/500. (SH:- Providing and laying 80mm thick interlocking paver blocks in km 21/735 to 21/790) Under PDNA-2023

Estimated cost:-423304/-only

Estimated Money:-9500/-only

Time:-Two Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	24.75	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	122641
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	302.50	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	287375
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge..	2.25	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	13288
Total						423304

DNT No./59 for the Year 2025-26, Checked & approved for Rs 423304/-Only

Executive Engineer,
B&R Division,
HP.PWD, Paonta Sahib.

Job 29.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages to Paonta Puruwalla Singhpura Bhagani Gojjar Dakpather road km 0/0 to 26/500. (SH:- Providing and laying 80mm thick interlocking paver blocks in km 14/165 to 14/220) Under PDNA-2023			Estimated cost:-422655/-only
			Estimated Money:-9500/-only
			Time:- Two Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4.8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	24.75	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	122641
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	302.50	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	287375
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.14	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	12639
Total						422655

DNT No/ ~~124~~ for the Year 2025-26, Checked & approved for Rs 422655/-Only

Executive Engineer,

B&R Division,

HP.PWD, Paonta Sahib.

Tab 30.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages to Jagatpur Parduni road km 0/0 to 5/00. (SH:- Providing and laying 80mm thick interlocking paver blocks in km 0/775 to 0/885) Under PDNA-2023

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	19.25	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	95388
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	385.00	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	365750
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge..	6.13	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	36203
Total						497340

DNIT No/6/ for the Year 2025-26, Checked & approved for Rs 497340/-Only

Executive Engineer,
B&R Division,
HP.PWD, Raonla Sahib.

Job 30.

Draft Schedule of Quantity

Name of Work:- Repair & Restoration of rain damages to Jagatpur Parduni road km 0/0 to 5/00. (SH:- Providing and laying 80mm thick interlocking paver blocks in km 0/775 to 0/885) Under PDNA-2023

Estimated cost:-497340/-only
Estimated Money:-10000/-only
Time:-Two Month

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1 :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	19.25	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	95388
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	385.00	Per square metre	950.00	Rupees Nine hundred fifty and paise nil only	365750
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	6.13	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	36203
Total						497340

DNIT No/5/ for the Year 2025-26, Checked & approved for Rs 497340/-Only

Executive Engineer,
B&R Division,
HP.PWD Raonla Sahib.