

**Himachal Pradesh
Public Works Department**

NO/PW/SNG/CB/E-16/Tender/25-26- 6032-56

Dated: - 26-11-2025

To

The Executive Engineer (IT Cell),
Nigam Vihar, H.P. Shimla-2.
cc-pwd-hp@nic.in


Subject: -Publication of Tender Notice.

Sir,

Enclosed please find herewith notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per notification Pr. Secy (PW) to the Govt of Himachal Pradesh Letter No. PBW(B)A(3)1/2020 dated Shimla -2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

Encl: -NIT and Schedule of Quantity

Yours faithfully,


Executive Engineer
Sangrah Division
HPPWD Sangrah

Copy forwarded to the following for information and necessary action :-

1. The Engineer -in- Chief, , HPPWD Shimla-2 please.
2. The Chief Engineer (SZ), HPPWD Shimla-2 please.
3. The Deputy Commissioner, Sirmaur Distt. Sirmour at Nahan Please.
4. The SDM Sangrah please.
5. The Superintending Engineer, 12th Circle HPPWD Nahan please.
6. The BDO Sangrah please.
7. All the Assistant Engineers under this division to display on their respective Notice Boards.
8. The Notice Board.


Executive Engineer
Sangrah Division
HPPWD Sangrah

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
SHORT TERM NOTICE INVITING TENDERS**

Sealed **percentage rate tenders** on from 6 & 8 are hereby invited by the Executive Engineer, Sangrah Division, HP.PWD. Sangrah on behalf of the Governor of H.P. for the following works from the approved and eligible contractors enlisted with HPPWD under revised rules:-

Tender Schedule:-

Date and time of receipt of application for tender form-01.12.2025 up to 04:00 PM

Date and time of issue/Sale of tender form-03.12.2025 up to 12:00 Noon

Date and time of receipt of tender form-03.12.2025 up to 02:30 PM

Date and time of opening tender form-03.12.2025 at 03:00 PM

The tender form can be had from the office of the Executive Engineer against Cash (**Non-refundable**). The earnest money should be in the shape of **Fixed Deposit** duly **pledged in favour of the Executive Engineer Sangrah Division HPPWD Sangrah** must accompany each tender. Conditional tender and the tender received without earnest money will summarily be reject. The offer will be kept open for **75 days. The Executive Engineer reserves the right to reject one or all tenders without assigning any reason.**

Sr. No.	Name of work	Estimated cost in Rs.	EMD in Rs.	Cost of Tender	Time Allowed	Class of Contractor
1.	Restoration of Rain Damages on Nohra Bogdhar Methli Road km. 0/00 to 34/00 (SH:- C/O R/wall from RD. 2/728 to 2/731.50 , 2/717 to 2/720.50 & 2/364 to 2/371.50 and C/O Drain from Km. 0/00 to 10/000 in essential reaches) Under PDNA 2023	362722	7,300/-	Rs. 350/-	03 Months	Class C & D
2.	Restoration of Rain Damages on Ratwa Gehel Road km. 0/00 to 3/400 (SH:- C/O R/Wall from km. 2/230 to 2/242 and P/L of G-II from km. 2/710 to 2/870 in damaged portion) Under PDNA 2023	416293	8400/-	Rs. 350/-	03 Months	Class C & D
3.	Restoration of Rain Damages on Ratwa Gehel Road km. 0/00 to 3/400 (SH:- C/O R/Wall from km. 3/020 to 3/032) Under PDNA 2023	315718	6,400/-	Rs. 350/-	03 Months	Class C & D

1. The contractors shall produce their latest registration/ renewal of their registration/ GST Registration / EPF No. and earnest money should be accompanied with application. Application without earnest money will not be entertained.
2. Ambiguous/ telegraphic/Conditional tenders or tender by fax/ E- mail shall not be entertained/ considered and will summarily be rejected. Tender received after due date and time will be rejected.
3. The offer shall remain valid up to **75 days**.
4. The contractor/bidder should quoted in percentage in words as well as in figures failing which XEN reserves the right to accept/ reject any or all tenders.
5. The contractor /bidders must inspect the site to ascertain /familiar the site conditions, accessibility etc. before quoting the bid/tender.
6. The tender documents shall be issued to only those contractors who does not have more the two works in hand in any HPPWD Circle/Division worth Rs. 1.00 Crore each.
7. That all your rates are inclusive of GST as such you will pay whole of it and you would not claim anything extra on this account from the Department.
8. The provisions of notification issued vide Additional Chief Secretary (PW) to the Govt. of HP. Shimla notification No. PBW (B) A (3)1/2018 dated 13.04.2021 shall also be applicable.

Provisions of the Addl. Chief Secretary (PW) to the Govt. of HP letter No. PBW(B)C(17)2/2012 dated 07.08.2018 are applicable.

The bidders are requested to submit their bid as per Notification issued by the Principal secretary PW to the Govt. of HP vide No. PBW(B)A(3)1/2020 dated 22.07.2020 & Govt. of HP vide No. PBW(B)A(3)1/2020-I dated 07.10.2021 and Engineer-in-Chief HPPWD Shimla-2 letter No. PW/CTR/32-20/Genl. Inst. CPWD/2020-37996-38095 dated 13.03.2023.


Executive Engineer,
Sangrah Division,
HP.PWD; Sangrah.

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-2 please.
2. The Chief Engineer (SZ) HPPWD Shimla-2 please.
3. The Deputy Commissioner Distt. at Nahan please.
4. The Superintending Engineers 12th Circle HPPWD Nahan please.
5. The SDM/BDO, Sangrah please.
6. All the Assistant Engineers under this Division.
7. The Drawing Branch of this office.
8. Notice Board.


Executive Engineer,
Sangrah Division,
HP.PWD, Sangrah.

Schedule of Quantity

Job No. 1

Name of Work:- Restoration of Rain Damages on Nohra Bogdhar Methili Road km. 0/00 to 34/00 (SH:- C/O R/wall from RD. 2/728 to 2/731.50 , 2/717 to 2/720.50 & 2/364 to 2/371.50 and C/O Drain from Km. 0/00 to 10/000 in essential reaches) Under PDNA 2023

Estimated Cost:

362722

Earnest Money:

7,300/-

Time Limit:

Three Months

Sr. No	Description of Item	Net Quantity	Unit	Rate		Amount	
				In Figure	In Words		
1	Excavation in soil in hilly area in all depths using manual means as per drawing and technical specification ministry of Rural Development for rural roads August 2004 (Two thousands four) clause 305.1 (three hundred five point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials including dressing of sides and bottom and back filling in trenches with excavated suitable materials and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places in specified manner, systematically with level consideration to avoiding a diverse effects on environment, trimming filling of unevenness blind age and finishing of the road to specified dimension or as directed by the Engineer-in-charge. any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	5.91	cubic metre	Per cubic metre	350.00	Rupees (Three Hundred fifty & Paise Zero) Only	2069
2	Excavation in foundation, trenches etc. in earth work in all heights and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiselling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required, setting out to required lines, levels as shown on the drawings and as directed by the Engineer-in-Charge at site, according to the HPPWD specification of 1990-Volume-I, and shorting out useful and un-useful materials and stacking the same in all leads, lifts and transportations of the usefull materials for filling in roadways embankments for grades improvements and levelling to required grades and then disposing of surplus excavated earth in acquired width of road on or approved dumping sites through all modes of transportation including head load animal load or mechanical means alongwith its levelling fine dressing and all labour, mechanies materials, tools, equipments and incidental necessary to complete the work by mechanized means and labour(if any required). All useful materials such as stone single, aggregate and slates shall be sorted out and stacked along road side to the maximum possible extends in all leads, lifts through all modes of transportation and all others incidental charges any loss to the public and private properties during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractors and shall have to be duly compensated by him in all respect including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	58.14	cubic metre	Per cubic metre	510.00	Rupees (Five Hundred ten & Paise Zero) Only	29651

3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and specification clause 802.803.1202 & 1203(PCC Grade M10 Nominal mix 1:3:6) 20mm (One Cement : three Sand: Six Graded Stone Aggregate) 20mm (Twenty Millimetre) including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	26.10	cubic metre	Per cubic metre	6002.91	Rupees (Six thousand two & Paise ninety one) Only	156676
4	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:4:8 (One Cement : Four Sand: Eight Graded Stone Aggregate) 40mm (Forty Millimetre) including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	34.41	cubic metre	Per cubic metre	4652.57	Rupees (Four Thousand six hundred fifty two & Paise fifty seven) Only	160095
5	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8. including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	2.14	cubic metre	Per cubic metre	978.00	Rupees (Nine hundred seventy eight & Paise zero) Only	2093
6	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia pvc pipe extending through the full width of the structure with slopes of (1V:20H) towards drawing face complete as per drawing and technical specification clause 614.709.1204.3.7. including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	42	No's	Each	289.00	Rupees (Two Hundred eighty nine & Paise zero) Only	12138
Total							362722

Signature of contractor with full address.

Quoted rate in figure (+/-)%)

Quoted rate in words (+/-)%)

Executive Engineer,
Sangraha Division,
HP.PWD. Sangraha.

Schedule of Quantity					Job No. 02		Estimated Cost:		416293	
Name of Work:- Restoration of Rain Damages on Ratwa Gehel Road km. 0/00 to 3/400 (SH:- C/O R/Wall from km. 2/230 to 2/242 and P/L of G-II from km. 2/710 to 2/870 in damaged portion) Under PDNA 2023							Earnest Money:		8,400/-	
							Time Limit:		Three Months	
Sr. No	Description of Item	Net Quantity	Unit		Rate		In Words		Amount	
					In Figure					
1	Excavation in soil in hilly area in all depths using manual means as per drawing and technical specification ministry of Rural Development for rural roads August 2004 (Two thousands four) clause 305.1 (three hundred five point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials including dressing of sides and bottom and back filling in trenches with excavated suitable materials and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places in specified manner, systematically with level consideration to avoiding a diverse effects on environment, trimming filling of unevenness blind age and finishing of the road to specified dimension or as directed by the Engineer-in-charge. any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	12.72	cubic metre		350.00		Rupees (Three Hundred fifty & Paise Zero) Only		4452	
2	Excavation in foundation, trenches etc. in earth work in all heights and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiselling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required, setting out to required lines, levels as shown on the drawings and as directed by the Engineer-in-Charge at site, according to the HPPWD specification of 1990-Volume-1, and shorting out useful and un-useful materials and stacking the same in all leads, lifts and transportations of the usefull materials for filling in roadways embankments for grades improvements and levelling to required grades and then disposing of surplus excavated earth in acquired width of road on or approved dumping sites through all modes of transportation including head load animal load or mechanical means alongwith its levelling fine dressing and all labour, mechanieries materials, tools, equipments and incidental necessary to complete the work by mechanized means and labour (if any required). All usefull materials such as stone single, aggregate and slates shall be sorted out and stacked along road side to the maximum possible extends in all leads, lifts through all modes of transportation and all others incidental charges any loss to the public and private properties during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractors and shall have to be duly compensated by him in all respect including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	16.80	cubic metre		510.00		Rupees (Five Hundred ten & Paise Zero) Only		8568	
3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 1:4:8 (One Cement : Four Sand: Eight Graded Stone Aggregate) 40mm (Forty Milimetre) including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	60.00	cubic metre		4700.95		Rupees (Four Thousand seven hundred & Paise nity five) Only		282057	

4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia pvc pipe extending through the full width of the structure with slopes of i(V):20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7 including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	30	No's	Each	289.00	Rupees (Two Hundred eighty nine & Paise zero) Only	8670
5	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8. including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	12.24	cubic metre	Per cubic metre	978.00	Rupees (Nine hundred seventy eight & Paise zero) Only	11971
6	Providing Laying, spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing rolling with 3-wheeled static roller 8-10 tonnes in stages to proper grade and camber applying and brooming crushable screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading - 2 as per technical specification clause 405 . WBM Grading- 11	42.08	cubic metre	Per cubic metre	2390.10	Rupees (Two thousand three hundred ninety & Paise ten) Only	100575
Total							416293

Signature of contractor with full address.

Quoted rate in figure (+/-)%)

Quoted rate in words (+/-)%)


Executive Engineer,
Sangrah Division,
HP.PWD. Sangrah.

Schedule of Quantity			Job No. 3		Estimated Cost:		315718
Name of Work:- Restoration of Rain Damages on Ratwa Gehel Road km. 0/00 to 3/400 (SH:- C/O R/Wall from km. 3/020 to 3/032) Under PDNA 2023			Earning Money:		6,400/-		Three Months
Sr. No	Description of Item	Net Quantity	Unit	Rate		Amount	
				In Figure	In Words		
1	Excavation in soil in hilly area in all depths using manual means as per drawing and technical specification ministry of Rural Development for rural roads August 2004 (Two thousands four) clause 305.1 (three hundred five point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials including dressing of sides and bottom and back filling in trenches with excavated suitable materials and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places in specified manner, systematically with level consideration to avoiding a diverse effects on environment, trimming filling of unevenness blind age and finishing of the road to specified dimension or as directed by the Engineer-in-charge. any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his on cost in all cases including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	12.72	cubic metre	350.00	Rupees (Three Hundred fifty & Paise Zero) Only	4452	
2	Excavation in foundation, trenches etc. in earth work in all heights and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiselling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required, setting out to required lines, levels as shown on the drawings and as directed by the Engineer-in-Charge at site, according to the HPPWD specification of 1990-Volume-1, and shorting out useful and un-useful materials and stacking the same in all leads, lifts and transportations of the usefull materials for filling in roadways embankments for grades improvements and levelling to required grades and then disposing of surplus excavated earth in acquired width of road on or approved dumping sites through all modes of transportation including head load animal load or mechanical means alongwith its levelling fine dressing and all labour, mechanieries materials, tools, equipments and incidental necessary to complete the work by mechanized means and labour(if any required). All usefull materials such as stone single, aggregate and slates shall be sorted out and stacked along road side to the maximum possible extends in all leads, lifts through all modes of transportation and all others incidental charges any loss to the public and private properties during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractors and shall have to be duly compensated by him in all respect including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	16.80	cubic metre	510.00	Rupees (Five Hundred ten & Paise Zero) Only	8568	

3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 1:4:8 (One Cement : Four Sand: Eight Graded Stone Aggregate) 40mm (Forty Millimetre) including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	60.00	cubic metre	Per cubic metre	4700.95	Rupees (Four Thousand seven hundred & Paise nity five) Only	282057
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia pvc pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 . including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	30	No's	Each	289.00	Rupees (Two Hundred-eighty nine & Paise zero) Only	8670
5	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8. including hauling/ carriage of all labours, equipments and materials to various locations through all mode of transportations in all leads, lifts to the entire satisfaction and direction of the Engineer- in - Charge.	12.24	cubic metre	Per cubic metre	978.00	Rupees (Nine hundred seventy eight & Paise zero) Only	11971
Total							315718

Quoted rate in figure (+/-)%

Quoted rate in words (+/-)%

Signature of contractor with full address.


Executive Engineer,
Sangrah Division,
HP.PWD. Sangrah.