

Himachal Pradesh
Public Works Department

NO/PW/TLD/Tender/2025:-
To

9062-71

Dated:- 22.11.2025

Executive Engineer IT Cell,
Nirman Bhawan, Nigam Vihar, Shimla-2


Subject:-

Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - NIT.


Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh


HPPWD Mandi for information please.

Copy is forwarded to Superintending Engineer, 1st Circle,

Copy to All the Assistant Engineers working under this Division.

Copy to AB/DB in this office.

Copy to Notice board.


Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"

Scaled Percentage tender on form No. 6&8 for the following works detailed in the table below hereby invited by the Executive Engineer, HPPWD Division (B&R), Thalout at Pandoh on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 01.12.2025 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative who wish to be present. The request for issuing tenders form along with earnest money must reach in his office up to 3.00 P.M. on 28.11.2025 and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 29.11.2025 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, HPPWD Division (B&R), Thalout at Pandoh during office hour on any working day.

Sr. No.	Name of work	Estima ted cost	Earnest money	Cost of form	Time Period	Form No.	Eligibil ity of Contra ctors
1	Maintenance of Four laining of End Pandoh bypass to Takoli Kullu Section of NH-21 Km. 222/700 to 227/600 (SH: Earthwork in filling at 223/300 to 223/400) Job No. 5	99980	2,000	Rs. 350/-	One month	6&8	-do-
2	RRD on Shalla Nallah to Khini road Km. 0/0 to 6/500 (SH: Hiring of Excavator cum loader for Removal of Slips/boulders, muck, debries etc. at various RDs)	99600	2,000	Rs. 350/-	One month	6&8	-do-
3	RRD Bouchari to Kandha road Km. 0/0 to 2/00 (SH: -Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
4	Restoration of rain damages on Thach to Kashod road Km. 0/00 to 6/500 (SH: Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at RD 3/00 to 6/500) Secetion-II	99600	2,000	Rs. 350/-	One month	6&8	-do-
5	RRD on road from Thalout to Kalhani Km. 0/0 to 11/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs between KM 5/000 to 11/000	99600	2,000	Rs. 350/-	One month	6&8	-do-
6	Repair and Maintenance of Govt. of Sen. Sec. School at Balichowki in Tehsil Balichowki Mandi (HP) (SH: P/L plaster for repair, M.S. grill, wooden windows, 6mm thick glass and painting steel work).	98667	2,000	Rs. 350/-	One month	6&8	-do-
7	RRD on Khanethi to Khuhan road Km. 0/0 to 2/00 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
8	RRD on Shalla Nallah Shara Odidhar Dhraunli road Km. 0/0 to 8/00 (SH: Hiring of excavator cum loader for removal of slips/debries/muck etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
9	RRD on Baggi to Kahsna road Km. 0/00 to 1/500 (SH: Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
10	RRD on Thalout to Kalahni road Km. 0/00 to 11/00 (SH: Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at various RDs) Job No. 1.	99600	2,000	Rs. 350/-	One month	6&8	-do-
11	RRD on Masar to Binoul road Km. 0/0 to 4/00 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in KM. 0/0 to 4/00).	99600	2,000	Rs. 350/-	One month	6&8	-do-
12	Maintenance of Four Laining of End Pandoh bypass to Takoli Kullu section of NH-21 (KM. 222/700 to 232/500) under NHDP-IVB on Hybride mode in the Himachal Pradesh (SH: Providing and Supplying WBM Grade-III between portion RDs km. 223/300 to 223/420) Job-I	98103	2,000	Rs. 350/-	One month	6&8	-do-

13	RRD on Thalout-Panjain-Thachi-Shattadhar road Km. 0/00 to 40/00 (SH: Hiring of Excavator cum loader for removal of slips/boulders, muck debris etc. at various RDs)	99600	2,000	Rs. 350/-	One month	6&8	-do-
14	RRD on Jala to Khini road km. 0/00 to 2/465 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panarsa Section) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-
15	RRD on Bouchari to Kandha road Km. 080 to 12/00 (SH: Hiring of Tipper for carriage/Disposal of slips in various Rds in Km. 5/00 to 6/00)	98000	2,000	Rs. 350/-	One month	6&8	-do-
16	A/R and M/O various roads under Pandoh Sub Division under Pandoh section-1(SH: Painting two coats on existing bridge railing and RCC slab culverts railing in various roads under Pandoh Section-I).	99909	2,000	Rs. 350/-	One month	6&8	-do-
17	RRD on Baggi to Kashna road Km. 0/00 to 1/500 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panarsa Section)	99600	2,000	Rs. 350/-	One month	6&8	-do-
18	RRD on road Khuhan to Didar km. 0/0 to 6/00 (SH: C/o R/Wall at RD 2/785 to 2/787).	99598	2,000	Rs. 350/-	One month	6&8	-do-
19	RRD on Thatta to Katwanoo road Km. 0/0 to 3/00 (SH: Hiring of excavator cum loader for removal of slips/debris/mucks etc. at various RDs) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-
20	RRD on Chamarjani to Sansoi road Km. 0/0 to 2/00 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-
21	RRD on Bouchari to Kandha road Km. 0/0 to 12/00 (SH: Hiring of Tipper for carriage/Disposal of slips in various Rds in km. 9/0 to 12/00)	98000	2,000	Rs. 350/-	One month	6&8	-do-
22	RRD on Jalal to Khini road Km. 0/0 to 2/465 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panarsa Section) Job No. 2	99600	2,000	Rs. 350/-	One month	6&8	-do-
23	RRD on Bhatludhar to Baggi road Km. 0/00 to 2/00 (SH: C/o R/Wall in PCC 1:4:8 at RD 0/097.30 to 0/101.30)	83249	2,000	Rs. 350/-	One month	6&8	-do-
24	RRD on road from Khuhan to Diddar km. 0/0 to 6/00 (SH: C/o R/Wall at RD 2/789 to 2/791)	99934	2,000	Rs. 350/-	One month	6&8	-do-
25	RRD on Pandoh-Takoli-Kullu bypass road Km. 222/700 to 227/600 (SH: Hiring of excavator cum loader for removal of slips/debris/mucks etc. at various RDs) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-
26	RRD on Bhatludhar to Baggi road Km. 0/00 to 2/00 (SH: C/o R/Wall in PCC 1:4:8 at RD 0/095 to 0/97.30).	83136	2,000	Rs. 350/-	One month	6&8	-do-
27	RRD on road from Sudhrani to Ghat Km 0/0 to 5/500 (SH: C/o wing wall at Thatta side for existing slab culvert at RD 0/180).	99966	2,000	Rs. 350/-	One month	6&8	-do-
28	R.R.D on Batwari to Rensh road km. 8/640 to 15/610 (SH: Hiring of excavator cum loader for removal of slips/debris mucks etc. at RD 12/500 to 15/910)	99600	2,000	Rs. 350/-	One month	6&8	-do-
29	RRD on Thalout to Kalhani road Km. 0/0 to 11/0 (SH: C/o B/wall in wire crates at RD 2/155 to 2/170).	99634	2,000	Rs. 350/-	One month	6&8	-do-

30	RRD on Jawalapur to Parashar road Km. 0/00 to 12/525 (SH: Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs) Job No. 2	99600	2,000	Rs. 350/-	One month	6&8	-do-
31	R.R.D on Khodathach to Jognigalu road Km. 0/0 to 3/00 (SH: Hiring of excavator cum loader for removal of slips/debris/mucks etc. at various RDs)	99600	2,000	Rs. 350/-	One month	6&8	-do-
32	Maintenance of Pandoh, Takoli Kullu by pass road old NH-21 Km. 222/700 to 227/600 (SH: - Providing and supplying WBM Grade-III between RDs 222/700 to 223/500) Job No. 1	98462	2,000	Rs. 350/-	One month	6&8	-do-
33	R.R.D on various roads under Balichowki Sub Division (SH:- Hiring of excavator cum loader for removal of slips/debris/mucks etc. at various RDs of Thachi Section)	99600	2,000	Rs. 350/-	One month	6&8	-do-
34	RRD on Dhamu to Masar road Km. 0/0 to 4/500 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in Km. 0/0 to 4/500).	99600	2,000	Rs. 350/-	One month	6&8	-do-
35	RRD on Ghirdha Khad to Guran road Km. 0/00 to 2/00 (SH: Hiring of excavator cum loader for removal of slips/debris/mucks etc. at various RDs)	99600	2,000	Rs. 350/-	One month	6&8	-do-
36	RRD on Chubhlu to Farsh road Km. 0/0 to 4/00 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-
37	RRD on Bhatludhar to Baggi road Km. 0/0 to 2/00 (SH: C/o B/Wall in PCC 1:4:8 at RD 0/097.50 to 0/105).	95022	2,000	Rs. 350/-	One month	6&8	-do-
38	Maintenance of Four Laining End Pandoh bypass to Takoli Kullu Section of NH-21 (KM. 222/700 to 232/500) under NHDP-IVB on Hybride mode in the Himachal Pradesh (SH: Providing and supplying WBM Grade-II between portion RDs Km. 223/300 to 223/420) Job-II	98234	2,000	Rs. 350/-	One month	6&8	-do-

TERMS & CONDITIONS:-

1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work Satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
4. The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh

NO/PW/TLD/Tender/2025:-

9052-61

Dated:-

22.11.2025



Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP.
3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
4. The Chief Engineer, (MZ) HPPWD Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD Mandi HP.
6. The Distt. Panchayat Officer Mandi HP.
7. All AEs under this Division.
8. The President of Contractor's Association.
9. Notice Board/Accounts Branch/Drawing Branch/Supdt. with spare copies.

Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh

Certificate

Certified that the tender called vide this office letter No. PW/TLD/Tender/2025- 9052-61 dated 22-11-2025 is emergent nature and in Public interest.


Executive Engineer,
HPPWD Division (B&R),
Thalout at Pandoh 


SCHEDULE OF QUANTITY

Name of work:-RRD on Shalla Nallah to Khini road Km 0/00 to 6/500 (SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDS)

Estimated Cost:-99600.00
Earnest Money:-2000.00


Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
	Quoted rate in figures					Total 99600.00
	Quoted rate in words					


 Executive Engineer,
 Thalout Division,
 HP PWD Thalout.

SCHEDULE OF QUANTITY
Name of work:- RRD Bounchari to Kandha road km 0/0 to 2/00 (SH: - Hiring of excavator cum loader
for removal of slips/debries/mucks etc. at various RDS).


S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words	Time:- One Month		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per dication of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hour	99600.00	
	Quoted rate in figures					Total	99600.00
	Quoted rate in words						


 Executive Engineer,
 Thalout Division,
 HP PWD Thalout

SCHEDULE OF QUANTITY
Name of work:- RRD on Khanethi to Khuhan road km 0/0 to 2/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDS).

Estimated Cost:-99600.00
 Earnest Money:-2000.00
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words	Hours		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unsevicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per drection of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00	
	Quoted rate in figures					Total	99600.00
	Quoted rate in words						


 Executive Engineer,
 Thalout Division,
 HP PWD Thalout


SCHEDULE OF QUANTITY

Name of work:- RRD on Shalla Nallah Shara Odidhar Dhraunli road km 0/0 to 8/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDS).

Estimated Cost:-99600.00
 Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words	Hours		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per drection of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationa staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00	
	Quoted rate in figures					Total	99600.00
	Quoted rate in words						


 Executive Engineer,
 Thalout Division,
 HP PWD Thalout


SCHEDULE OF QUANTITY

Name of work:-RRD on Baggi to Kahsna road Km 0/00 to 1/500 (SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at various RDs)

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unsevicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
	Quoted rate in figures					
	Quoted rate in words					
					Total	99600.00



 Executive Engineer,
 Thaloat Division,
 HP PWD Thaloat

SCHEDULE OF QUANTITY

Name of work:- RRD on Masar to Binoul road km 0/0 to 4/00 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in km 0/0 to 4/00).

Estimated Cost:-99600.00
 Earnest Money:-2000.00
 Time:- One Month

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words	Hours		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00	
	Quoted rate in figures					Total	99600.00
	Quoted rate in words						



Executive Engineer,
 Thalout Division,
 HP PWD Thalout

SCHEDULE OF QUANTITY

Name of work:-Maintenance of Four Lining of End Pandoh bypass to Takoli Kullu section of Nh-21 (KM 222/700 to 232/500) under NHDP-IVB on Hybride mode in the Himachal Pradesh. (SH:-Providing and supplying WBM Grade-III between portion RDs Km 223/300 to 223/420), Job-I

Estimated cost:-98103.00
 Earnest Money:-2000.00
 Time:- One Month


Sr.No	Description of item	Quantity	Rate		Unit	Amount
			in figure	in words		
1	Providing, laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per technical specification clause 405 by Mechanical means . within all leads , lifts, carriage of materials and other incidental complete.	37.50	2616.08	Rs. Two Thousand Six hundred Sixteen and paise Eight only	Per Cubic metre	98103.00
Total in figures						98103.00
	Quoted rate in figure					
	Quoted rate in words					


 Executive Engineer,
 Thalout Division
 HP PWD Thalout

SCHEDULE OF QUANTITY
Name of work:-RRD on road Khuhuan to Didar km 0/0 to 6/00 (SH :- C/O R/wall at RD 2/785 to 2/787.)

Estimated Cost :- 99,598.00
Earnest Money :- 2000.00
Time :- One Month

Sr. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	9.03	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	3596.00
2	Providing and laying in position cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate) bedding of specified grade including shuttering complete within all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.44	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	6337.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:4:8 (one cement: four sand: eight graded stone aggregate 40mm nominal size) as per entire satisfaction and direction of Engineer-in-Charge.	0.87	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	4256.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 Coursed rubble masonry in cement mortar 1:6 (one cement: six sand) complete within all leads, lifts carriage of material and other incidentals. 2nd sort.	9.93	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	51608.00
5	Construction of Randum Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.29	3751.20	Rs. Three thousand seven hundred fifty one and paise twenty	Per Cubic Metre	31097.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	2.14	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	2704.00
Total in figures						99598.00
Rate quoted by contractor +/-				Percent		
Quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Thalour Division,
 HPPWD, Thalour


SCHEDULE OF QUANTITY

Name of work:- RRD on Bounchari to Kandha road km 0/0 to 12/00 (SH:-Hiring of Tipper for carriage /Disposal of slips in various Rds in km 9/0 to 12/00).

Estimated Cost:-98000.00
Earnest Money:-2000.00

Time:- One Month

S. No	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words			
	Hiring of Tipper for carriage of debris/ muck / unservicable material from the various reaches of the road including all leads, lifts and unloading of material at suitable places as per entire satisfaction of Engineer-in-Charge (9.00 am to 5.00 pm)	28	3500	Rupees Three thousand five hundred only		Per day	98000
	Terms and conditions:-						
	1. The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge.						
	2. During working hours any type of accident the owner is responsibal						
	3. Driver will be provided by the owner.						
	Quoted rate in figures						
	Quoted rate in words						
						Total	98000.00


 Executive Engineer,
 Thalout Division (B&R),
 HP PWD Thalout.


SCHEDULE OF QUANTITY

Name of work:- RRD on Jala to Khini road Km 0/100 to 2/465 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panarsa Section) Job No.2

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per dication of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
	Quoted rate in figures				Total	99600.00
	Quoted rate in words					


 Executive Engineer,
 Thalout Division
 HP PWD Thalout

Kashmir Singh

SCHEDULE OF QUANTITY
Name of work:- RRD on road from Khuhuan to Diddar Km. 0/0 to 6/00 (SH :- C/O R/wall at RD 2/789 to 2/791)

Estimated Cost:- 99,934.00
Earnest Money :- 2000.00
Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth-work in excavation for structures as per drawing and technical specification clause 305-1 including setting out, construction of shorting and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.62	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	3432.00
2	Providing and laying in position cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate) bedding of specified grade including shuttering complete within all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.44	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	6337.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 in cement concrete 1:4:8 (one cement: four sand: eight graded stone aggregate 40mm nominal size) as per entire satisfaction and direction of Engineer-in-Charge.	0.87	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	4256.00
4	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement: six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	9.93	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only	Per cubic metre	51608.00
5	Construction of dry rubble stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.29	3751.20	Rupees Three thousand seven hundred fifty one and	Per Cubic Metre	31097.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	2.14	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	2704.00
Total in figures						99434.00
			Percent			
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Thalot Division (B&R),
HPPW/D, Thalot


SCHEDULE OF QUANTITY

Name of work:- R.R.D. on Pandoh-Takoli-Kullu bypass road Km 222/700 to 227/600. (SH: - Hiring of excavator cum loader for removal of slips/debris/mucks etc. at various RDs.) Job-1

Estimated Cost:-99,600.00
Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
	Quoted rate in figures				Total	99600.00
	Quoted rate in words					


 Executive Engineer,
 Thalout Division
 HP PWD Thalout

Name of work:- RRD on road from Sudhrani to Ghat km 0/0 to 5/500 (SH:- C/O wing wall at Thatta side for existing slab culvert at RD 0/180).

SCHEDULE OF QUANTITY

Description of item

Estimated Cost:- 99966.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	2.64	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	1051
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone aggregate) 40 mm (forty millimetre) nominal size in open foundation complete as per drawing and technical specification Clause 802.803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	18.14	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	88734
3	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	5.00	391.20	Rs. Three hundred ninety one and paise Twenty only	Nos.	1956
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	6.51	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	8225
Total						99966.00
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP, PWD, Thalout.

Name of work:- R.R.D. on Batwari to Rensh road km 8/640 to 15/910. (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 12/500 to 15/910.)

SCHEDULE OF QUANTITY

Estimated Cost:-99,600.00	
Earnest Money:-2000.00	
Time:- One Month	

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
	Quoted rate in figures				Total	99600.00
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout.

Name of work: RRD on Thalout to Kalhani road Km. 0/0 to 11/0 (SH- C/O B/wall in wire crates at RD. 2/155 to 2/170)

SCHEDULE OF QUANTITY

Sr No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm indepth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	36.75	139.40	Rupees One hundred thirty nine and paise forty only.	Per Cubic Metre	5123.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shorting and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	4.32	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	1720.00
3	Providing and laying of Boulder apron laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (one hundred millimetre x one hundred millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighing not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.51	3254.70	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	92791.00
Total in figures						
			Rate quoted by contractor +/-			
			Quoted rate in gigure			
			Quoted rate in words			
Total						99634.00

Estimated Cost :- Rs. 99,634.00
Earnest Money :- 2000.00
Time :- One Month


Executive Engineer,
Thalout Division (B&R),
HPPWD, Thalout

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli Kulliu by pass road old NH-21 km 222/700 to 227/600 (SH:-
Providing and supplying WBM Grade-III between RDS 222/700 to 223/500) Job No-1

Estimated cost:-98462.00
Earnest Money:-2000.00
Time:- One Month

Sr.No	Description of item	Quantity	Rate		Unit	Amount
			in figure	in words		
1	Providing, laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per technical specification clause 405 by Mechanical means, within all leads, lifts, carriage of materials and other incidental complete.	38.00	2591.10	Rs. Two Thousand five hundred ninety one and paise ten only	Per Cubic metre	98462.00
Total in figures						98462.00
Rate quoted by contractor +/-						
Quoted rate in figure						
Quoted rate in words						



 Executive Engineer
 Thalout Division
 HP PWD Thalout.

SCHEDULE OF QUANTITY

Name of work:- RRD on Dhamu to Masar road km 0/0 to 4/500 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDS in km 0/0 to 4/500).

Estimated Cost:-99600.00
 Earnest Money:-2000.00
 Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operation staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
	Quoted rate in figures				Total	99600.00
	Quoted rate in words					


 Executive Engineer,
 Thalout Division,
 HP PWD Thalout.

Name of work:- RRD on Ghirdha Khad to Gurran road Km 0/00 to 2/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs)

SCHEDULE OF QUANTITY

S. No.	Description of item	Qty.	Figure	Rate in		Unit	Amount
				Words	Time:- One Month		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationa staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Month	Per Hours	99600.00
	Quoted rate in figures						99600.00
	Quoted rate in words						
	Total						

Executive Engineer,
Thalout Division,
HP PWD Thalout

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhatudhar to Baggi road Km. 0/0 to 2/000 (SH:- C/O B/wall in PCC 1:4:8 at RD. 0/097.50 to 0/105)

Estimated Cost :- 95,022.00
Earnest Money :- 2000.00
Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm indepth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	33.68	139.40	Rupees One hundred thirty nine and paise forty only.	Per Cubic Metre	4694.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3.15	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	1254.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	17.25	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	84380.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	12	391.20	Rupees Three hundred ninety one and paise twenty only	Each	4694.00
Total in figures					Total	95022.00
				Percent		
				Rate quoted by contractor +/-		
				Quoted rate in gigure		
				Quoted rate in words		


Executive Engineer,
Thalout Division (B&R),
HPPWD Thalout

SCHEDULE OF QUANTITY

Name of work:-Maintenance of Four Laining of End Pandoh bypass to Takoli Kullu section of Nh-21 (KM 222/700 to 232/500) under NHDP-IVB on Hybride mode in the Himachal Pradesh. (SH:-Providing and supplying WBM Grade-III between portion RDS Km 223/300 to 223/420). Job-II

Estimated cost:-98234.00
 Earnest Money:-2000.00
 Time:- One Month

Sr.No	Description of item	Quantity	Rate		Unit	Amount
			in figure	in words		
1	Providing, laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per technical specification clause 405 by Mechanical means . within all leads , lifts, carriage of materials and other incidental complete.	37.55	2616.08	Rs. Two Thousand Six hundred Sixteen and paise Eight only	Per Cubic metre	98234.00
Total in figures						98234.00
	Quoted rate in figure					
	Quoted rate in words					


 Executive Engineer,
 Thalout Division
 HP PWD Thalout