



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Offline

No. PWD-TD/TA/Tender /2025-26 11293-95

Dated: - 14-11-2025

To


The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Tissa Division, HPPWD,
Tissa.


Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Tissa Division, HPPWD,
Tissa.

Certificate

Certified that the tenders called vide this office letter No. PWD-TD/TA/Tender /2024-25:- 1192-11292 dated. 14-11-2025 is emergent nature due to heavy rain and clouds burst on several places and in Public interest.


Executive Engineer,
Tissa Division, HPP/W/D,
Tissa.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"**

Scaled Percentage/Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Tissa Division, HPPWD, Tissa behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

Date of issued/sale of tender form against

21-11-2025.

Date of opening of Tender:-

22-11-2025.

The tender shall be received upto 11.00 AM on **22-11-2025** and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against E-Challan as shown below (Nonrefundable) during the working hours on **21-11-2025.**

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Tissa Division, HPPWD, Tissa a must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

Job No	Name of Work	Estimated cost.	Earnest Money	Time Limit	Cost of Form	Eligible Class
1	Restoration of rain damages on various road under Tissa Sub Division (SH:- Hiring of JCB for removal of slips at various Rds)	99910	2000	Two Month	350	D/C
2	Restoration of rain damages on various road under Tissa Sub Division (SH:- Hiring of JCB for removal of slips at various Rds)	99910	2000	Two Month	350	D/C
3	Restoration of rain damages on various road under Tissa Sub Division (SH:- Hiring of JCB for removal of slips at various Rds)	99910	2000	Two Month	350	D/C
4	Restoration of rain damages on various roads under Tissa Sub-Division (SH:- Hiring of Tractor with Trolley for removal of slips.	96000	2000	Two Month	350	D/C
5	Restoration of rain damages on various roads of under Nakrot Sub-Division (SH:- Hiring of JCB for removal of slips at various Rd's	98880	2000	Two Month	350	D/C
6	Restoration of rain damages on various roads of under Nakrot Sub-Division (SH:- Hiring of JCB for removal of slips at various Rd's	99910	2000	Two Month	350	D/C
7	Restoration of rain damages on various roads of under Nakrot Sub-Division (SH:- Hiring of JCB for removal of slips at various Rd's	99910	2000	Two Month	350	D/C
8	Restoration of rain damages on various roads of Kalhel Section of under Nakrot Sub-Division (SH:- Hiring of JCB for removal of slips at various Rd's	99425	2000	Two Month	350	D/C
9	Restoration of rain damages on various roads of Kalhel Section of under Nakrot Sub-Division (SH:- Hiring of JCB for removal of slips at various Rd's	98400	2000	Two Month	350	D/C
8	Restoration of rain damages on Khakhri to Ail road Km 0/0 to 17/780 (SH:-Providing B/wall at Rd 4/362 to 4/372)	98850.	2000	Two Month	350	D/C
9	A/R & M/O Residential building quarter II and III at Koti (under Koti Sub Division (SH:-Repair work of celling	75057.20	2000	Two Month	350	D/C

Distemping and painting)

	Restoration of rain damages due to OFC on Tissa Bairagarh (Portion Tissa Satyas) road Km 0/0 to 7/0 (SH:- Providing B/wall at Rd 4/957 to 4/964)	95579	2000	Two Month	350	D/C
11	Restoration of rain damages on Khakhri to Ail road Km 0/0 to 17/780 (SH:-Providing B/wall at Rd 4/350 to 4/360)	99942	2000	Two Month	350	D/C
12	Restoration of rain damages due to OFC on Tissa Bairagarh (Portion Tissa Satyas) road Km 0/0 to 7/0 (SH:- Providing B/wall at Rd 4/950 to 4/957)	95315	2000	Two Month	350	D/C
13	C/o approach road to newly construction Add. Rest House at Bhanjraru (SH:- Providing railing work bat Rd 0/070 to 0/100)	99873.20	2000	Two Month	350	D/C
14	C/o approach road to newly construction Add. Rest House at Bhanjraru (SH:- Providing railing work bat Rd 0/100 to 0/130)	99877	2000	Two Month	350	D/C
15	Restoration of rain damages on various road under Trella Sub Division (SH:- Hiring of JCB for removal of slips at various Rds)	99910	2000	Two Month	350	D/C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
3. GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.



Executive Engineer
Tissa Division HPPWD
Tissa at Bhanjraru

Dated:- 14-11-2025

No.PW.TD.CB.TA.Tender Notice/2025-26- 11193-11292

Copy to the following for information for information please: -

1. Engineer-in-Chief HPPWD Shimla.
2. Chief Engineer(KZ) HPPWD Dharamshala.
3. The Superintending Engineer 7th Circle HPPWD Dalhousie.
4. All Executive Engineers in HPPWD.
5. SDM Tissa.
6. All the Assistant Engineer working under Tissa Division.
7. Tehsildar/BDO Tissa.
8. SHO Tissa.
9. All the contractors.
10. Notice Board.


Executive Engineer
Tissa Division HPPWD
Tissa at Bhanjraru

PRICE SCHEDULE

PRICE SCHEDULE

Estimated cost-	99910.00
Fairnest money-	1998.20

Estimated cost-	99910.00
Fairnest money-	1998.20

Sr. No.	Description / items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-seviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, state tax/GST or any other taxes imposed by the Government.	97.00	Per Hour	1030.00	Rupees One Thousand Thirty Only	99910.00	Nine Thousand Nine Hundred Ten Only
					Total:-	99910.00	Rupees Ninety Nine Thousand Nine Hundred Ten Only
	Quoted Rate in figure (%)				(To be quoted by Contractor)		
	Quoted Rate in Words (%)				(To be quoted by Contractor)		

PHI appeared for Re 99910/- only.
(Ninety nine thousand nine hundred
and ten only.)

~~Executive Engineer~~
Tissa Division, HP.PWD.,
at Bhanjiraru

D.N.I.T.

Estimated Cost Rs. = 99910.00
 Earnest Money Rs. = 2000.00
 Time Limit = One Months

Name of work:- Restoration of rain damages on various roads under Tissa Sub-Division (SH:-
 Hiring of JCB for removal of slips at various Rd's

S.N.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In words		
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-servicable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	97.00	1030.00	Rupees One Thousand Thirty Only	Per Hour	99910.00
		Total				99910.00

Assistant Engineer
 Tissa Sub-Division
 HP PWD Tissa

DNIT Approved for Rs 99910/- only.
 (Ninety nine thousand nine hundred ten only.)

Assistant Engineer
 Tissa Division, HP.PWD,
 at Bharanasi

D.N.I.T.

Name of work:- Restoration of rain damages on various roads under Tissa Sub-Division (SH:-

Hiring of JCB for removal of slips at various Rd's

Estimated Cost Rs. = 99910.00
 Earnest Money Rs. = 2000.00
 Time Limit = One Months

S.N.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In words		
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-servicable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	97.00	1030.00	Rupees One Thousand Thirty Only	Per Hour	99910.00
Total						99910.00

File
 Assistant Engineer
 Tissa Sub-Division
 HP PWD Tissa

*QNTT Approved for RS 99910/-only.
 (Ninety nine thousand nine hundred
 den only.)*

File
 Assistant Engineer
 Tissa Division, HP PWD,
 at Dhanpalli

D.N.I.T.					
Name of work:- Restoration of rain damages on various roads under Tissa Sub-Division (Sh:- Hiring of Tractor with Trolley for carriage of stones/debris/muck/unserviceable material in various reaches.					Estimated Cost Rs. =
					Earnest Money Rs. =
					Time Limit =
					One Months
S.N.	Description of item	Quantity	Rate		Unit
			In Fig.	In words	Amount
1	Hiring of tractor with trolley including operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. the break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	24.00	4000.00	Rupees Four Thousand Only	Per day
Total					96000.00

Assistant Engineer
Tissa Sub Division
HPPWD. Tissa

Executive Engineer
Tissa Division, HPPWD.
at Phampana

DNIT Approved for Rs 96000/- only
(Twenty six thousand only).

Percentage BOQ
PRICE SCHEDULE

PRICE SCHEDULE

Name of works:- Restoration of rain damages on various roads under Naka of Sub-Division (SI)- Hiring of JCB for removal of slips at various Rd.s)
2,5000.85/10/000000

PRICE SCHEDULE									
Name of work:- Restoration of rain damages on various roads under Nakot Sub-Division (S.D.). Hiring of ICB for removal of slips at various Rd's)									
Sr. No.	Description/Items of work.	Quantity	Unit	Rate		Estimated cost-	One Month		
				Figures	Words	Amount in figure	Amount in words		
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the owner. The repair and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	96.00	Per Hour	1030.00	Rupees One Thousand Thirty Only	98880.00	Rupees Ninety Eight Thousand Eight Hundred Eighty Only		
						Total:-	98880.00	Rupees Ninety Eight Thousand Eight Hundred Eighty Only	
						(To be quoted by Contractor)			
						(To be quoted by Contractor)			

Q11T appeared for RS 988861 only.
Piney eight thousand eight only.

[Signature]

Percentage Book

PRICE SCHEDULE

Name of work:- Restoration of rain damages on various roads under Nakrot Sub-Division (SM:- Hiring of JCB for removal of slips at various Rd's)

Estimated cost: 99910.00
Farnest money: 1998.20

Sr. No.	Description /Items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax/GST or any other taxes imposed by the Government.	97.00	Per Hour	1030.00	Rupees One Thousand Thirty Only	99910.00	Rupees Ninety Nine Thousand Nine Hundred Ten Only
Total:-						99910.00	Rupees Ninety Nine Thousand Nine Hundred Ten Only

Quoted Rate in figure (%)	(To be quoted by Contractor)
Quoted Rate in Words (%)	(To be quoted by Contractor)

QMR Approved for RS 99910/- only.
(Private when the house and when hundred
Gen. only.

Engineer
Road Division, NPPWD,
at Bhaugana

Percentage Bid			
PRICE SCHEDULE			
Name of work:- Restoration of rain damages on various roads under Nakrol Sub-Division (SI:- Hiring of JCB for removal of slips at various Rd's)			
Estimated cost-	99910.00	Earnest money-	1998.20

PRICE SCHEDULE	Name of work:- Restoration of rain damages on various roads of Kathel Section under Nakrol Sub-Division (SIH--fitting of JCB for removal of slips at various Rd's)
1	1000
2	1000
3	1000
4	1000
5	1000
6	1000
7	1000
8	1000
9	1000
10	1000
11	1000
12	1000
13	1000
14	1000
15	1000
16	1000
17	1000
18	1000
19	1000
20	1000
21	1000
22	1000
23	1000
24	1000
25	1000
26	1000
27	1000
28	1000
29	1000
30	1000
31	1000
32	1000
33	1000
34	1000
35	1000
36	1000
37	1000
38	1000
39	1000
40	1000
41	1000
42	1000
43	1000
44	1000
45	1000
46	1000
47	1000
48	1000
49	1000
50	1000
51	1000
52	1000
53	1000
54	1000
55	1000
56	1000
57	1000
58	1000
59	1000
60	1000
61	1000
62	1000
63	1000
64	1000
65	1000
66	1000
67	1000
68	1000
69	1000
70	1000
71	1000
72	1000
73	1000
74	1000
75	1000
76	1000
77	1000
78	1000
79	1000
80	1000
81	1000
82	1000
83	1000
84	1000
85	1000
86	1000
87	1000
88	1000
89	1000
90	1000
91	1000
92	1000
93	1000
94	1000
95	1000
96	1000
97	1000
98	1000
99	1000
100	1000

Removal of slips at various Rd's)

removal of slips at various Rd's)									
Sr. No.		Description/Items of work.	Quantity	Unit	Estimated cost-		Earnest money-		
					Time limit-		One Month		
					Figures	Rate	Amount in figure	Amount in words	
1		Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	97.00	Per Hour	1025.00	Rupees One Thousand Twenty Five Only	99425.00	Rupees Ninety Nine Thousand Four Hundred Twenty Five Only	
Total:-							99425.00	Rupees Ninety Nine Thousand Four Hundred Twenty Five Only	
		Quoted Rate in figure (%)	(To be quoted by Contractor)						
		Quoted Rate in Words (%)	(To be quoted by Contractor)						

Handwritten signature in red ink.

~~Assistant Engineer~~
Tissa Division, HEPWD,
at Bhasparau

Percentage Bid
PRICE SCHEDULE

Name of work:- Restoration of rain damages on various roads of kailhel Section under Nakrol Sub-Division (SR - Hiring of JCB for removal of slips at various Rd's)

Sr. No.	Description /Items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-servicable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	96.00	Per Hour	1025.00	Rupees (One Thousand Twenty Five Only)	98400.00	Rupees Ninety Eight Thousand Four Hundred Only
						Total:-	

Quoted Rate in figure (%)	(To be quoted by Contractor)
Quoted Rate in Words (%)	(To be quoted by Contractor)

Our approval is given for the work at Nakrol Sub-Division for the restoration of rain damages on various roads of kailhel Section under Nakrol Sub-Division.

Executive Engineer
Tissa Division, H.P.W.D.
at Bhatnagar

Percentage BOD

PRICE SCHEDULE

Name of work:- Restoration of rain damages on Khabut to All road km 0/0 to 17/780 (Sh- Providing B/wall at Rd 4/362 to 4/372

Sr. No.	Description /Items of work.	Quantity	Unit	Estimated cost		One Month	
				Figures	Words	Amount in Figure	Amount in words
				Rate			
1	Excavation in hilly area in all heights and depths and in all soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302.1603.1 and 1603.2 and sorting out useful materials and stacking the same within all leads and lifts in acured width of road and transportation of un-useful material for filling in road ways camber, embankments for grade improvements and disposal of all surplus material to approved dumping site through all mods of transportation as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	63.84	Per Cubic Metre	200.00	Rupees Two Hundred Only	12768.00	Rupees Twelve Thousand Seven Hundred Eighty Eight Only
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and	5.60	Per Cubic Metre	300.00	Rupees Three Hundred Only	1680.00	Rupees One Thousand Six Hundred Eighty Only

3	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimeter) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS: two hundred eighty) and IS: 4826 (IS: four thousand eight hundred twenty six) in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints, laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 or as per the directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. the rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	31.26	Per cubic metre	2700.00	Rupees Two Thousand Seven Hundred Only	84402.00	Rupees Eighty Four Thousand Four Hundred Two Only
					Total:-	98850.00	Rupees Ninety Eight Thousand Eight Hundred Fifty Only
	Quoted Rate in figure (%)				(To be quoted by Contractor)		
	Quoted Rate in Words (%)				(To be quoted by Contractor)		

Rate approved for Rs 98850/-
 Rs Ninety Eight thousand & Eighty
 (Ninety Eight) only.


 Executive Engineer
 Tissa Division, H.P.P.W.D.,
 at Bhanjiraru

Percentage BOD

PRICE SCHEDULE

Name of work:- A/R & M/O to Residential building quarter II and III at Koti (under Koti Sub-

Estimated Cost Rs.= 75057.20

Division. (SH:- Repair work of ceiling Distemping and painting.

Earnest Money Rs.= 1501.14

Time Limit = One Month

S.N.	Description of item	Quantity	Rate		Unit	Amount	Amount in words
			In Fig.	In words			
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, T-iron and frame 50x50x6 mm (fifty into fifty into six millimetre) including cutting, hoisting, fixing in position and applying priming coat of approved steel primer all complete as per the directions of Engineer-in-Charge including carriage of material in all leads and lifts and other incidentals. The rate is including royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government.	56.70	90.00	Rupees Ninety Only	Per cum	5103.00	Rupees Five Thousand One Hundred Three Only
2	Providing and fixing plain multipurpose cement board (High pressure steam cured) with suitable screws from cement particle board in ceiling etc. complete (frame work to paid separately) 6mm (six millimetre) thick cement fiber board as per the directions of Engineer-in-Charge including carriage of material in all leads and lifts and other incidentals. The rate is including royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government.	9.80	600.00	Rupees Six Hundred Only	per sqm	5880.00	Rupees Five Thousand Eight Hundred Eighty Only
3	Providing and applying white cement based putty of average thickness 2mm (two millimetre) of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete as per the directions of Engineer-in-Charge including carriage of material in all leads and lifts and other incidentals. The rate is including royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government.	151.35	140.00	Rupees One Hundred Forty Only	per sqm	21189.00	Rupees Twenty One Thousand One Hundred Eighty Nine Only
4	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade (two or more coats) over and including water thinable priming coat with cement primer as per the directions of Engineer-in-Charge including carriage of material in all leads and lifts and other incidentals. The rate is including royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government.	151.35	100.00	Rupees One Hundred Only	per sqm	15135.00	Rupees Fifteen Thousand One Hundred Thirty Five Only
5	Painting wood work with Deluxe multi surface paint to give an even shade two or more coats applied at the rate 0.90 ltr. (zero decimal nine litre) per 10 sqm. (ten square metre) over an under coat of primer applied at the rate 0.80 (zero decimal eight) litre per 10 sqm. (ten square metre) of approved brand and manufacture. as per directions of Engineer-in-Charge including carriage of material in all leads and lifts and other incidentals. The rate is including royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government.	110.24	105.00	Rupees One Hundred Five Only	per sqm	11575.20	Rupees Eleven Thousand Five Hundred Seventy Five And Paise Twenty Only

6	Painting G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade new work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution as per directions of Engineer-in-Charge including carriage of material in all leads and lifts and other incidentals. The rate is including royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government.	102.50	110.00	Rupees One Hundred Ten Only	per sqm	11275.00	Rupees Eleven Thousand Two Hundred Seventy Five Only
7	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS: 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid as per directions of Engineer-in-Charge including carriage of material in all leads and lifts and other incidentals. The rate is including royalty, Malkana, Toll	1.00	4900.00	Rupees Four Thousand Nine Hundred Only	per sqm	4900.00	Rupees Four Thousand Nine Hundred Only
					Total	75057.20	Rupees Seventy Five Thousand Fifty Seven And Paise Twenty Only
	Quoted Rate in figure (%)				(To be quoted by Contractor)		
	Quoted Rate in Words (%)				(To be quoted by Contractor)		

Rate appearing for Rs 75057.20 only
 Rs Seventy Five thousand fifty
 Seven & paise twenty only

Executive Engineer
 Tissa Division, H.P.W.D.,
 at Bhanjra

Percentage Bid

PRICE SCHEDULE

Name of work:- Restoration of damages due to laying of OTC on Tissa to Bahraganah (Portion Tissa to Sanyas) road km 0/0 to 7/0 (SH- Providing B/wall at Rd 4/957 to 4/964)

Sr. No.	Description /Items of work.	Quantity	Unit	Figures	Rate	Words	Amount in Figure	Amount in words
1	Excavation in hilly area in all heights and depths and in all soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rockhard rock chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302.1603.1 and 1603.2 and sorting out useful materials and stacking the same within all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways camber, embankments for grade improvements and disposal of all surplus material to approved dumping site through all modes of transportation as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	24.33	Per Cubic Metre	180.00	Rupees One Hundred Eighty Only		8379.00	Rupees Four Thousand Three Hundred Seventy Nine Only
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	7.28	Per Cubic Metre	280.00	Rupees Two Hundred Eighty Only		2038.00	Rupees Two Thousand Thirty Eight Only

Estimated cost- 75579.00
Earnest money- 1911.28
Time limit- One Month

3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced cement concrete in open foundation for all type of structure such as Retaining walls, Breast walls etc of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40 mm (forty millimetre) nominal size in or under water and curing complete for 14 (fourteen) days including pumping or bailing out water, (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying water complete for all heights and depths including cost of form work as per drawing and MORID technical specification clause 802.803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.40	Per Cubic Metre	5500.00	Rupees Five Thousand Five Hundred Only	7700.00	Rupees Seven Thousand Seven Hundred Only
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (One cement isto Six coarse sand isto Twelve graded stone aggregate 20 mm (Twenty Millimetre) nominal size upto plinth level with Cement mortar 1:6 (One cement isto Six coarse sand) and curing complete, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government	14.42	Per cubic metre	4260.00	Rupees Four Thousand Two Hundred Sixty Only	61429.00	Rupees Sixty One Thousand Four Hundred Twenty Nine Only
5	Construction of dry rubble Masonry for Retaining Walls, Breast Walls, Revement Walls and Parapets etc. For sub structure and super Structure complete as per Drawing and Technical Specification Clause 704.6 and 1302.50 as per directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Govt.	8.71	Per cubic metre	2300.00	Rupees Two Thousand Three Hundred Only	20133.00	Rupees Twenty Thousand Thirty Three Only
				Total:-	95579.00		Rupees Ninety Five Thousand Five Hundred Seventy Nine Only
(To be quoted by Contractor)							
(To be quoted by Contractor)							
Quoted Rate in figure (%)							
Quoted Rate in Words (%)							

But Appen 2 for 95500 only
 9 Nine Five Thousand Five Hundred
 Seventy Nine only

Executive Engineer
 Tissa Division, HPPV/D,
 at Dhaka.

PRICE SCHEDULE

PRICE SCHEDULE

Name of work: Restoration of rain damages on Chalcid to All road km 0/0 to 17/780 (SH. Providing P/w all at Rd 4/370 to 4/160)

Estimated cost	99962.00
Earliest money	1994.84
Time limit	One month

Description / Items of work.	Quantity	Unit	Rate	
			Amount in	Amount in
St.				

[illegible]

1	Excavation in hilly area in all heights and depths and in all soil by manual/ mechanical means for (undisturbed saturated soil comprising of ordinary soil, soft rock, hard rock chiselling, wedging, roof of tree & (wherever blasting is prohibited) and their intermediate classification of soil complete including setting out zone for the required lines, grades, width cutting and finishing of side slopes and level as shown at site.	608 ETO	Poor/ Fair Marble	2500 MM	Hollowed Taper Hollowed Taper	1447.000	Begun: Thirteen Thousand Six Hundred Twenty Five
---	---	---------	----------------------	---------	----------------------------------	----------	---

and required to be placed in the same manner as the material directed by Engineer-in-Charge at site according to the MORD Technical Specification Clause 102.340.1.1 and 1603.2 and sorting out useful materials and stacking the same within all leads and lifts in secured width of road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvements and disposal of all surplus material to approved dumping site through all modes of transportation as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.

2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock,	6.40	Per Cubic Metres	100.00	Suppose Three Hundred Only	19.20.00	Suppose One Thousand With Hundred Two
---	--	------	------------------	--------	----------------------------	----------	---------------------------------------

have rock chiseling / weeding out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other detriorous materials and disposal of materials upto any level and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all levels, lifts and other incidentals. The rate

3	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimeter) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS:two hundred eighty) and IS: 4826 (IS: four thousand eight hundred twenty six) in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints, laid with stone boulders weighing not less than 25 kg. (Twenty five kilogram) each as per drawing and technical specification clause 1301 or as per the directions of Engineer-in-Charge including cartage of materials within all heads and lifts and other incidentals, be rate including the octroi, royalty, Matsana, toll tax, sale tax GST or any other taxes imposed by the Government.	31.26	Per cubic metre	27,000.00	Rupees Two Thousand Seven Hundred (only)	(Rs.40,2.00)	Rupees Eight Four Thousand Four Hundred Two Only
---	---	-------	-----------------	-----------	--	--------------	--

[illegible]

Nine Thousand
Nine Hundred
Forty Two

(Handwritten signature)

Quoted Rate in Figure (%)

To be signed by Contractor

To be signed by Contractor

Excellency

[Faint handwritten notes, possibly bleed-through from the reverse side.]

100

Percentage Bid
PRICE SCHEDULE
Name of work: Restoration of damages due to laying of OTC on Tissa to Baharath (Portion Tissa to Satyas) road km 0/0 to 7/0 (5th).
Providing B/wall at Rd 4/950 to 4/957)

Sr. No.	Description /Items of work.	Quantity	Unit	Figures	Rate	Words	Amount in	Amount in
				Figures	Rate	Words	Figures	words
1	Excavation in hilly area in all heights and depths and in all soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302.1603.1 and 1603.2 and sorting out useful materials and stacking the same within all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways camber, embankments for grade improvements and disposal of all surplus material to approved dumping site through all modes of transportation as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	22.86	Per Cubic Metre	180.00	Rupees One Hundred Eighty Only	One Hundred Eighty	113.00	Rupees Four Thousand One Hundred Fifteen Only
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	7.28	Per Cubic Metre	280.00	Rupees Two Hundred Eighty	Two Hundred Eighty	2038.00	Rupees Two Thousand Thirty Eight Only

3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced cement concrete in open foundation for all type of structure such as Retaining walls, Breast walls etc of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40 mm (forty millimetre) nominal size in or under water and curing complete for 14 (fourteen) days including pumping or hauling out water, (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying water complete for all heights and depths including cost of form work as per drawing and MORD technical specification clause 802.803.1202 and 1203 or as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	1.40	Per Cubic Metre	5500.00	Rupees five Thousand Five Hundred Only	7700.00	Rupees Seven Thousand Seven Hundred Only
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (One cement isto Six coarse sand isto Twelve graded stone aggregate 20 mm (Twenty Millimetre) nominal size upto plinth level with Cement mortar 1:6 (One cement isto Six coarse sand) and curing complete, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	14.42	Per cubic metre	4260.00	Rupees Four Thousand Two Hundred Sixty Only	61429.00	Rupees Sixty One Thousand Four Hundred Twenty Nine Only
5	Construction of dry rubble Masonry for Retaining Walls, Breast Walls, Revetment Walls and Parapets etc. For sub structure and super Structure complete as per Drawing and Technical Specification Clause 704.6 and 1302.50 as per directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Govt.	8.71	Per cubic metre	2300.00	Rupees Two Thousand Three Hundred Only	20033.00	Rupees Twenty Thousand Thirty Three Only
					Total:-	95315.00	Rupees Ninety Five Thousand Three Hundred Fifteen Only
(To be quoted by Contractor)							
(To be quoted by Contractor)							

(3)

Percentage Book

PRICE SCHEDULE

Name of Work:- C/o approach road to newly construction Add. Rest House at Bhanjiraru (Sh:- Providing railing work at Rd 0/070 to 0/100)

S.N.	Description of item	Quantity	Unit	Estimated Cost Rs. =		Earnest Money Rs. =		Time Limit =	
				In Fig.	Words	Amount	Amount	One Month	Amount
1	Excavation in hilly area in all heights and depths and in all soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302.1603.1 and 1603.2 and sorting out useful materials and stacking the same within all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways camber, embankments for grade improvements and disposal of all surplus material to approved dumping site through all modes of transportation as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	3.15	Per Cubic metre	400.00	Rupees Four Hundred Only	1260.00	Rupees One Thousand Two Hundred Sixty Only		
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced cement concrete in open foundation/sub structure for all type of structure of plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40 mm (forty millimetre) nominal size in or under water and curing complete for 14 (fourteen) days including pumping or bailing out water, (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying water complete for all heights and depths including cost of form work as per drawing and MORD technical specification clause 802.803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	1.58	Per Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	9164.00	Rupees Nine Thousand One Hundred Sixty Four Only		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven decimal five) up to all floor level in cement mortar 1:6 (one cement isto six coarse sand) and curing complete as per directions of Engineer-in-Charge including carriage of material in all leads and lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Govt.	3.62	Per Cubic metre	10200.00	Rupees Ten Thousand Two Hundred Only	36924.00	Rupees Thirty Six Thousand Nine Hundred Twenty Four Only		
4	Providing/fabrication steel work of (Tata / Sail) riveted, bolted or welded work in built up sections trusses and framed work including cutting, hoisting fixing in position and applying a priming coat of red lead paint in gratings, framed guard bars, ladders, railing brackets complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Toll Tax Sales tax and any other taxes imposed by the Government.	3.52	Per qtl	10200.00	Rupees Ten Thousand Two Hundred Only	35904.00	Rupees Thirty Five Thousand Nine Hundred Four Only		

5	Providing and fixing GI wire mesh 50x503mm on vertical post for fencing including all necessary nuts and bolts complete as directed by the Engineer-In-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Toll Tax Sales tax and any other taxes imposed by the Government.	43.74	Per Square mtr	380.00	Rupees Three Hundred Eighty Only	16621.20	Rupees Sixteen Thousand Six Hundred Twenty One And Paise Twenty Only
Quoted Rate in figure (%)		(To be quoted by Contractor)			Total	99873.20	Rupees Ninety Nine Thousand Eight Hundred Seventy Three And Paise Twenty Only
Quoted Rate in Words (%)		(To be quoted by Contractor)					

*Don't approve the 99873.20
As myself have eight hundred
Seventy three & paise twenty only*

[Signature]
Executive Engineer
Tissa Division, H.P.P.W.D.,
at Bahararu

Percentage Bid

PRICE SCHEDULE

Name of Work:- C/o approach road to newly construction Add. Rest House at Bhanjara (SH:- Providing railing work at Rd 0/100 to 0/130

S.N.	Description of item	Quantity	Unit	In Fig.	Rate		Amount	Amount
					Words	Time Limit =		
						Estimated Cost Rs. =	99877.00	
						Earnest Money Rs. =	1997.54	
							One Month	
1	Excavation in hilly area in all heights and depths and in all soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock/hard rock chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same within all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways camber, embankments for grade improvements and disposal of all surplus material to approved dumping site through all modes of transportation as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government	3.15	Per Cubic metre	400.00	Rupees Four Hundred Only	1260.00	Rupees One Thousand Two Hundred Sixty Only	
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced cement concrete in open foundation/sub structure for all type of structure of plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40 mm (forty millimetre) nominal size in or under water and curing complete for 14 (fourteen) days including pumping or bailing out water, (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying water complete for all heights and depths including cost of form work as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government	1.58	Per Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	9164.00	Rupees Nine Thousand One Hundred Sixty Four Only	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven decimal five) up to all floor level in cement mortar 1:6 (one cement isto six coarse sand) and curing complete as per directions of Engineer-in-Charge including carriage of material in all leads and lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Govt.	3.62	Per Cubic metre	10200.00	Rupees Ten Thousand Two Hundred Only	36924.00	Rupees Thirty Six Thousand Nine Hundred Twenty Four Only	
4	Providing/fabrication steel work of (Tata / SAIL) riveted, bolted or welded work in built up sections trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in gratings, framed guard bars, ladders, railing brackets complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Toll Tax Sales tax and any other taxes imposed by the Government	3.52	Per qtl	10200.00	Rupees Ten Thousand Two Hundred Only	35904.00	Rupees Thirty Five Thousand Nine Hundred Four Only	

5	Providing and fixing GI wire mesh 50x503mm on vertical post for fencing including all necessary nuts and bolts complete as directed by the Engineer-In-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Toll Tax Sales tax and any other taxes imposed by the Government.	43.75	Per Square mtr	380.00	Rupees Three Hundred Eighty Only	16625.00	Rupees Sixteen Thousand Six Hundred Twenty Five Only
				Total		99877.00	Rupees Ninety Nine Thousand Eight Hundred Seventy Seven Only
Quoted Rate in figure (%)		(To be quoted by Contractor)					
Quoted Rate in Words (%)		(To be quoted by Contractor)					

BMR approved for Rs 99877 only
 of 210000 wire from 200000 Budget
 seventy seven only.

Executive Engineer
 Tissa Division, H.P.W.D.,
 at Bhanjara

Estimated Cost Rs. =	99910.00
----------------------	----------

Earnest Money Rs. =	2000.00
Time Limit =	One Months

2000.00
One Mor

DLIT Approved for RS: 99910-
CReps: Ninety Nine Thousand Nine
Hundred Ten only

Executive Engineer
Tissa Division HPPWD
Tissa